

Before the Minnesota Public Utilities Commission

State of Minnesota

In the Matter of the Application of Minnesota Power  
for Authority to Increase Rates for Electric Utility  
Service in Minnesota

Docket No. E015/GR-16-664

Exhibit \_\_\_\_\_

**TRANSMISSION & DISTRIBUTION**

November 2, 2016

## Table of Contents

	Page
I. INTRODUCTION .....	1
II. TESTIMONY OVERVIEW .....	3
III. TRANSMISSION AND DISTRIBUTION OVERVIEW .....	3
A. Transmission Function Overview .....	4
B. Distribution Function Overview .....	8
IV. POWER DELIVERY CAPITAL INVESTMENTS .....	9
A. Transmission Capital Investments .....	9
1. Transmission Base .....	14
2. Reliability Requirement .....	15
a. Badoura 115 kV Transmission Project .....	15
b. Savanna 115 kV Transmission Project .....	18
c. Deer River 115 kV Transmission Project .....	21
d. Straight River 115 kV Transmission Project .....	26
e. NERC Required Projects .....	28
f. North Shore Loop .....	35
3. New Business or Customer Need .....	40
a. Nashwauk 230 kV/115 kV Transmission Facility Projects .....	40
b. 39 Line 115 kV Transmission Facility Project .....	45
c. Canisteo 115kV Transmission Facility Project.....	51
4. Regional Expansion Projects .....	54
a. Bemidji – Grand Rapids 230 kV Transmission Project.....	54
b. Monticello – Fargo 345 kV Transmission Facility Project.....	57
B. Distribution Capital Investments .....	59
1. Distribution Infrastructure .....	62
2. Advanced Metering Infrastructure and Technologies.....	64
3. Customer Service CIS/CC&B Capital Project.....	66
V. POWER DELIVERY O&M EXPENSE BUDGETS .....	68
A. Transmission O&M Expense Budget .....	69
B. Distribution O&M Expense Budget.....	70
C. Vegetation Management .....	70
D. Storm Restoration .....	72

Table of Contents  
(cont'd)

	Page
VI. OTHER COMPLIANCE REQUIREMENTS .....	74
A. FERC Return on Equity .....	74
B. MISO Participation .....	76
VII. COST CONTAINMENT EFFORTS .....	77
VIII. CONCLUSION.....	81

1 **I. INTRODUCTION**

2 **Q. Please state your name and business address.**

3 A. My name is Christopher E. Fleege, P.E. My business address is 30 West Superior  
4 Street Duluth, MN 55802.  
5

6 **Q. By whom and in what capacity are you employed?**

7 A. I work for ALLETE, Inc., doing business as Minnesota Power (“Minnesota Power” or  
8 the “Company”). My current position is Minnesota Power Vice President,  
9 Transmission and Distribution. I also provide executive leadership for Customer  
10 Service Operations which includes the Minnesota Power: Call Center, Credit &  
11 Collections, and the Customer Care & Billing (“CC&B”) Systems.  
12

13 **Q. Please summarize your educational and professional background.**

14 A. I graduated from the University of North Dakota with a degree in civil engineering. I  
15 have also earned a Master of Business Administration from the University of  
16 Minnesota–Duluth. I joined Minnesota Power in 1991 as a Civil Engineer and  
17 became a Supervising Engineer in 1998. In 1999, I was promoted to Manager of  
18 Engineering Services and led the corporate engineering department until accepting  
19 full responsibility for the Rapids Energy Center-UPM steam facility operation in  
20 Grand Rapids, Minnesota in 2004. I was promoted to General Manager of  
21 Renewable Operations in 2006 and was responsible for Minnesota Power’s  
22 hydroelectric power, co-generation, and wind operations, including construction of  
23 the Taconite Ridge Energy Center. I was promoted to President of Superior Water,  
24 Light & Power (“SWL&P”) in August of 2008, and to my current position in April  
25 2010. I am a licensed professional engineer in Minnesota.  
26

27 **Q. What are your job responsibilities for Minnesota Power as they relate to this  
28 proceeding?**

29 A. In my current position, I provide the leadership and direction for day-to-day activities  
30 of groups responsible for the power delivery, or transmission and distribution,  
31 (“T&D”) systems and our customer service operations at Minnesota Power. In

1 addition, I am responsible for the development and integration of strategic and  
2 operational plans that fulfill Minnesota Power’s business strategies and regulatory  
3 requirements as they relate to power delivery. I am responsible for ensuring that we  
4 operate and maintain our transmission and distribution systems to optimize Minnesota  
5 Power’s system’s capability, performance, and reliability. I am also responsible for  
6 ensuring we provide our customers with safe, reliable, and cost-effective products and  
7 services.

8

9 **Q. Have you sponsored any other comments or testimony before regulatory**  
10 **commissions?**

11 A. Yes. I have testified on behalf of ALLETE before the Federal Energy Regulatory  
12 Commission (“FERC”) in Docket No. ER11-134-000 concerning ALLETE’s request  
13 for: (1) 100 percent construction work in progress (“100% CWIP Recovery”); and  
14 (2) recovery of abandoned plant costs (“Abandoned Plant Recovery”) for two  
15 CapX2020 projects in which ALLETE was a participant. Specifically, ALLETE  
16 requested, and FERC granted, 100% CWIP Recovery and Abandoned Plant Recovery  
17 for the: (1) 68-mile, Bemidji, Minnesota to Grand Rapids, Minnesota 230 kV Project  
18 (“Bemidji Project”); and (2) 250-mile, Fargo, North Dakota to Monticello, Minnesota  
19 345 kV Project (“Fargo Project”).<sup>1</sup> I also provided testimony on behalf of ALLETE  
20 before FERC in Docket No. ER16-118-000 concerning ALLETE’s request for 100%  
21 CWIP Recovery for the Great Northern Transmission Line (“GNTL”), a 224-mile,  
22 500 kV transmission line between a point on the Minnesota-Manitoba border,  
23 northwest of Roseau, Minnesota, and Minnesota Power’s existing Blackberry  
24 Substation near Grand Rapids, Minnesota.<sup>2</sup>

25

---

<sup>1</sup> See *ALLETE, Inc.*, 133 F.E.R.C. ¶ 61,270 (2010). The Fargo Project includes both the Fargo, North Dakota to St. Cloud, Minnesota 345 kV Transmission Project (Docket No. E002,ET2/TL-09-1056) and the St. Cloud, Minnesota to Monticello, Minnesota 345 kV Transmission Project (Docket No. ET2,E002/TL-09-246).

<sup>2</sup> See *Midcontinent Indep. Sys. Operator & ALLETE, Inc.*, 153 F.E.R.C. ¶ 61,296 (2015).

1 **II. TESTIMONY OVERVIEW**

2 **Q. Please summarize your testimony in this proceeding.**

3 A. I provide testimony on the Company’s power delivery systems, including capital  
4 investment and operations and maintenance (“O&M”) expenditures. My testimony  
5 includes information that supports Minnesota Power’s prudent investment in local  
6 and regional capital projects and maintenance of our power delivery systems. I am  
7 also providing testimony on compliance items related to the FERC return on equity  
8 (“ROE”) dockets and the benefits of the Company’s participation in the Midcontinent  
9 Independent System Operator, Inc. (“MISO”). Finally, I provide testimony on the  
10 Company’s cost containment efforts as they relate to the transmission, distribution,  
11 and customer service departments.  
12

13 **Q. Are you sponsoring any exhibits in this proceeding?**

14 A. Yes. I am sponsoring the following exhibits:

- 15 • Exhibit \_\_\_ (CEF), Schedule 1 – Transmission Capital Investment Table
- 16 • Exhibit \_\_\_ (CEF), Schedule 2 – North Shore Loop Transmission System
- 17 • Exhibit \_\_\_ (CEF), Schedule 3 – Bemidji Project Cost Summary
- 18 • Exhibit \_\_\_ (CEF), Schedule 4 – Storm Restoration Cost Information
- 19 • Exhibit \_\_\_ (CEF), Schedule 5 – Wholesale Transmission Revenues and  
20 Expenses
- 21 • Exhibit \_\_\_ (CEF), Schedule 6 – Summary of Cost Control Efforts Related to  
22 Power Delivery and Customer Service
- 23 • Exhibit \_\_\_ (CEF), Schedule 7 – Service Center Map  
24

25 **III. TRANSMISSION AND DISTRIBUTION OVERVIEW**

26 **Q. What are the responsibilities of Minnesota Power’s Transmission and  
27 Distribution Department?**

28 A. The Transmission and Distribution Department is responsible for the maintenance,  
29 management, and construction of Minnesota Power’s power delivery systems so that  
30 energy is safely and reliably transmitted from generating resources (both Company-  
31 owned and third-party owned) to the distribution systems serving our customers. It is

1 also responsible for the residential and small commercial customer experience from  
2 meter to billing.

3  
4 Minnesota Power owns and operates an integrated transmission system that has  
5 facilities primarily in Minnesota and portions in North Dakota. Minnesota Power  
6 also operates a distribution system in northeastern Minnesota. The Transmission and  
7 Distribution Department is focused on ensuring that the integrated power delivery  
8 system is safe, reliable, and cost-effective.

9  
10 **Q. Are there any other groups that are within your responsibilities?**

11 A. Although the Communications Infrastructure (“CI”) and Support Services groups  
12 report directly to the Chief Operating Officer for Minnesota Power, all the  
13 responsibility for the groups’ capital and O&M budgets are managed through the  
14 Transmission and Distribution Department’s budgeting, approval process, and  
15 controls. Both groups are almost entirely co-located within the Transmission and  
16 Distribution Department. The CI group builds, operates, and maintains the  
17 Company’s CI and systems, including Computer Networks, Voice Over Internet  
18 Phones (“VOIP”), Mobile Radio System, Synchronous Optical Network (“SONET”),  
19 Microwave System, and Energy Management System, including the Supervisory  
20 Control and Data Acquisition System (“SCADA”). The Support Services group  
21 includes: Fleet, Stores, Facility Management, Vegetation Management, and  
22 Purchasing. The Support Services group provides centralized strategic sourcing and  
23 other supply chain efficiencies. These services are critical to T&D operations and  
24 work closely with my leadership team in the implementation of efficiency  
25 improvements and cost containment efforts that I discuss later in my testimony.

26  
27 **A. Transmission Function Overview**

28 **Q. Please describe the areas within the transmission function and their key**  
29 **functions.**

30 A. There are five (5) different areas entirely within the transmission function. These  
31 areas are:

- 1 (1) Power delivery, relay, and transmission structural engineering, responsible for  
2 substation field engineering, construction support for capital projects, and  
3 developing reliability-centered maintenance programs to ensure the health and  
4 reliability of Company transmission assets;
- 5 (2) System performance and planning, responsible for life-cycle planning,  
6 transmission system planning and budgeting, and addressing wholesale  
7 customer transmission service concerns;
- 8 (3) Tech systems, responsible for providing Company field personnel to self-  
9 perform construction, maintenance, and emergency repairs for transmission  
10 assets;
- 11 (4) Project management organization (“PMO”) and transmission business  
12 support, responsible for managing capital projects, programs, and portfolios  
13 through the life-cycle of a project, including all phases of capital project  
14 construction and negotiated transmission service-related contracts with  
15 generators, transmission owners, and other distribution utilities; and
- 16 (5) System operations, responsible for transmission operations for Minnesota  
17 Power and SWL&P.

18  
19 **Q. What are the primary transmission capital investments that have contributed to**  
20 **Minnesota Power’s need for a rate case?**

21 A. It has been seven years since Minnesota Power filed its last rate case. Minnesota  
22 Power has made significant capital investments over that time. These capital  
23 investments include: (1) investments in transmission projects for which recovery of  
24 some costs have been sought under Minnesota Power’s Transmission Cost Recovery  
25 Rider (“TCR”); and (2) investments in small- to medium-sized incremental  
26 transmission projects for system reliability, new business or customers, and  
27 increasing requirements for transmission base projects.

28  
29 **Q. Please describe Minnesota Power’s transmission assets.**

30 A. Minnesota Power is a vertically-integrated electric utility that owns and operates  
31 electric transmission facilities in portions of Minnesota and North Dakota. SWL&P,



1 a Minnesota Power subsidiary, provides electric service to its retail customers and  
2 owns transmission facilities in Wisconsin. Together, Minnesota Power and SWL&P  
3 respectively own an integrated transmission system comprised of approximately  
4 2,921 miles of alternating-current (“AC”) transmission facilities operating at voltages  
5 between 115 kilovolts (“kV”) and 500 kV, and approximately 177 transmission and  
6 distribution substations (the “Transmission System”). Minnesota Power and SWL&P  
7 are transmission-owning members of MISO. The integrated Transmission System  
8 has been under the functional control of MISO since it began operations in February  
9 2002. Service on the Minnesota Power and SWL&P Transmission System is open  
10 access, and transmission service reservations can be requested and approved under  
11 the terms of the MISO Tariff.

12  
13 Minnesota Power also owns and operates a high-voltage direct-current (“HVDC”) system that has a nominal rating of 550 megawatts (“MW”) at 250 kV. The 465-mile  
14 DC line connects the converter terminals in Center, North Dakota and Duluth,  
15 Minnesota. Minnesota Power acquired 100 percent ownership of the HVDC system  
16 in January 2010. It is used primarily to transmit wind energy from Center, North  
17 Dakota to Duluth, Minnesota.<sup>3</sup>

18  
19  
20 **Q. Please describe the drivers of Minnesota Power’s transmission investments.**

21 A. It is imperative that the Company maintain and improve the reliability of our  
22 Transmission System. To achieve this, we are continually studying our Transmission  
23 System to identify projects that are necessary to comply with mandatory reliability  
24 standards set by the North American Electric Reliability Corporation (“NERC”) and  
25 FERC.

26  
27 Many of our transmission facilities were placed in service during the 1960s and 1970s  
28 and are reaching the end of their useful life. Over the next years, we will continue to

---

<sup>3</sup> See *In the Matter of Minn. Power’s Petition to Purchase Square Butte Cooperative’s Transmission Assets and for Restructuring Power Purchase Agreements from Milton R. Young Unit 2 Generating Station*, ORDER GRANTING PETITION WITH CONDITIONS, Docket No. E015/PA-09-526 (Dec. 21, 2009).

1 examine our existing facilities and make the necessary upgrades to ensure reliability  
2 is not jeopardized. As we upgrade these aging assets, we will do so with an eye  
3 towards modernization by installing facilities that allow operators to monitor and  
4 respond quickly to maintenance needs and outages on the Transmission System.  
5

6 **Q. Have any recent events resulted in changes in the way the Company evaluates its**  
7 **transmission assets?**

8 A. Yes. Minnesota Power has identified a number of local transmission upgrades that  
9 will be required as the Company transitions our generation fleet to meet the  
10 *EnergyForward* generation targets that will impact our smaller coal generating  
11 stations.  
12

13 In addition, the nation's generation mix is anticipated to undergo unprecedented  
14 changes in response to the U.S. Environmental Protection Agency's ("EPA") Clean  
15 Power Plan and other market forces. Minnesota Power will continue to work with  
16 other utilities in the region and with MISO to identify and develop the necessary  
17 transmission improvements. Our proactive investment in the Transmission System  
18 will provide our customers access to least-cost and diverse generation resources.  
19

20 Finally, Minnesota Power has undertaken additional evaluations related to  
21 Transmission System security. The decision to undertake this evaluation was a result  
22 of a 2013 sniper attack in California that knocked out 17 large transformers that  
23 powered Silicon Valley.  
24

25 **Q. Can you describe the customers served by the Transmission System?**

26 A. The Transmission System serves the following two customer groups: (1) retail native  
27 loads; and (2) the loads of other investor-owned utilities, cooperatives, and municipal  
28 load-serving entities, or wholesale customers. The wholesale customers comprise  
29 approximately 16.5 percent of the total demand on the Minnesota Power  
30 Transmission System, with the remaining demand comprised of retail native load  
31 customers. From a transmission planning and transmission service perspective, our

1 retail customers and the wholesale customers require the same level of service, and as  
2 a result, the system is planned to serve the needs of each type of customer equally.

3  
4 **Q. Please describe MISO and its role with respect to the Transmission System.**

5 A. The Company is a transmission-owning member of MISO. This means that while  
6 Minnesota Power owns and maintains transmission assets, MISO operates the  
7 combined system, in conjunction with the transmission systems of the other 50  
8 transmission owners. Furthermore, MISO establishes: (1) the process and rules for  
9 wholesale customers to access the Transmission System on a non-discriminatory  
10 basis; (2) the annual transmission planning process for expanding or upgrading the  
11 regional transmission system, which includes the Transmission System (i.e., MISO  
12 Transmission Expansion Plan (“MTEP”)); and (3) the policies and procedures that  
13 provide for the allocation of costs incurred to construct certain transmission upgrades  
14 and the distribution of revenues associated with those costs.

15  
16 **B. Distribution Function Overview**

17 **Q. Please describe the Minnesota Power distribution system.**

18 A. The distribution system includes substation, transformers, wires, poles, metering, and  
19 other equipment involved in delivering energy products and services to our electric  
20 customers. Minnesota Power’s distribution system is comprised of over 5,800 miles  
21 of distribution lines, 201 distribution substations, and approximately 125,000 poles  
22 owned by Minnesota Power along with another approximately 25,000 poles used by  
23 Minnesota Power but owned by others (“Distribution System”). These assets serve  
24 approximately 145,000 electric customers across northeastern and central Minnesota.  
25 The region spans over 26,000 square miles from International Falls in the north to  
26 Royalton in the south and from Duluth in the east to as far west as the Long Prairie  
27 and Park Rapids communities. The customer areas are geographically separated by  
28 long distances.

29

1 **Q. Describe the distribution function objectives.**

2 A. The distribution function is responsible for the safe and reliable delivery of energy  
3 from the Transmission System to our customers. There have been recent examples  
4 that demonstrate the critical services and mission that the distribution function plays  
5 in providing and restoring service to customers. Hurricane Sandy and the following  
6 tropical storm caused approximately 8.5 million customers in the mid-Atlantic and  
7 Northeast to lose power. Through mutual aid agreements, we sent our distribution  
8 crews to the impacted areas to restore service for over three weeks in 2012. Closer to  
9 home, we have dispatched our crews to assist Xcel Energy dozens of times over the  
10 past six years, during storm events in the Twin Cities and in southern Wisconsin. In  
11 July 2016, we requested mutual aid from as far away as Missouri to address  
12 widespread outages experienced by approximately 46,000 Minnesota Power  
13 customers as a result of the worst storm to affect the Company's power delivery  
14 system in the Duluth area for at least 15 years.

15  
16 **Q. Please describe the organization and responsibilities of the distribution function.**

17 A. The distribution function is structured around the following key groups: Operations,  
18 Engineering, Business Operations, and Planning and Performance.

19  
20 Minnesota Power serves customers by making prudent investments in the Distribution  
21 System to add capacity, maintain and improve reliability, and replace assets as  
22 necessary to maintain safe system performance. We also perform routine  
23 maintenance activities on the Distribution System, which lowers the cost of operation  
24 over the long term and helps mitigate reliability issues.

25  
26 **IV. POWER DELIVERY CAPITAL INVESTMENTS**

27 **A. Transmission Capital Investments**

28 **Q. What is the purpose of this section of your testimony?**

29 A. In this section, I outline the historic capital investments made to the Transmission  
30 System and discuss the key capital projects being placed in service prior to the end of  
31 the 2017 test year. Cost estimates, unless otherwise noted, do not include allowance

1 for funds used during construction (“AFUDC”) or indirect project costs, including  
2 internal Minnesota Power overheads and labor allocations. Final and adjusted costs,  
3 unless otherwise noted, include AFUDC and all project internal costs. All costs,  
4 actuals, budgets, or forecasts are Total Company,<sup>4</sup> unless otherwise noted.  
5 Additionally, for projects with original cost estimates provided to the Minnesota  
6 Public Utilities Commission (“Commission”) in either a Route Permit or Certificate  
7 of Need (“CoN”) proceeding, I provide final costs that have been adjusted, using the  
8 Handy-Whitman Index, to the dollars (year) in which we provided the original  
9 estimate.

10

11 **Q. What type of capital investments are made by transmission?**

12 A. Minnesota Power’s capital investments fall into two types. The first are large capital  
13 projects that are often multi-year projects. These projects are capital-intensive and  
14 are aimed at improving the Transmission System, upgrading existing facilities to meet  
15 NERC compliance requirements and to accommodate new generation, replacing  
16 aging facilities, and making improvements to communication infrastructure and  
17 physical security.

18

19 The second are smaller capital projects done over a shorter period of time. These  
20 smaller projects make up a majority of the total number of projects that the  
21 transmission function completes each year. However, these smaller projects make up  
22 only a minor part of our overall capital budget.

23

24 Both of these capital project categories require investments in transmission line  
25 components, such as poles, conductors, switches, relays, and land rights for  
26 transmission line easements. They also include investments in substation  
27 components, such as transformers, capacitor banks, circuit breakers, remote terminals,  
28 and real property.

29

---

<sup>4</sup> “Total Company” refers to total Minnesota Power regulated, without Minnesota Power’s non-regulated entities.

1 **Q. Since the last Minnesota Power rate review was filed, what were the**  
2 **transmission function's key strategic goals driving the Company's capital**  
3 **investments?**

4 A. The transmission function is focused on maintaining the reliability and resiliency of  
5 the Transmission System. Since 2010, the Company's planned capital investments  
6 have been attributed to major regional expansion and reliability projects, such as the  
7 CapX2020 group of projects<sup>5</sup> and other regional reliability projects. The CapX2020  
8 projects are 230 kV and 345 kV transmission line projects that provide necessary  
9 upgrades to the regional transmission system to support local reliability, regional  
10 reliability, and renewable generation outlet. Prior to the CapX2020 projects, there  
11 had not been a major upgrade to the upper Midwest's electric transmission grid in  
12 nearly 40 years. These CapX2020 regional expansion projects were developed and  
13 vetted through the MISO MTEP regional transmission planning processes. Our  
14 investments in regional reliability projects are discussed in more detail later in my  
15 testimony.

16  
17 The Company also serves a disproportionately-higher percentage of industrial  
18 customers, when compared to other Minnesota utilities. These industrial customers  
19 have historically operated at a high capacity factor. These larger industrial customers  
20 are in the competitive mining and forest product industries. These customers are  
21 often interconnected at transmission voltages and, therefore, fall under the NERC  
22 operating and reliability requirements. Over the past five years, the Company has  
23 been actively supporting a significant number of customer interconnection requests  
24 from these larger industrial and wholesale customers.

25  
26 **Q. What is the regulatory overlay with respect to system reliability?**

27 A. Maintaining Transmission System reliability involves compliance with NERC  
28 reliability standards. In 2007, FERC granted NERC the legal authority to enforce  
29 reliability standards on all transmission owners. There are now over 100 mandatory

---

<sup>5</sup> Minnesota Power participated in the Bemidji Project and the Fargo Project. There are two other 345 kV transmission projects in the CapX2020 group of projects in which Minnesota Power did not participate.

1 reliability standards and over 1,000 sub-requirements, and NERC is actively engaged  
2 in assessing penalties, both monetary and non-monetary for noncompliance. To  
3 comply with NERC reliability standards, we continuously study the system because  
4 changes in load growth, generation mix, and existing transmission infrastructure can  
5 occur each year. These changes can impact whether upgrades are needed to maintain  
6 NERC compliance.

7

8 **Q. How does the transmission function categorize its capital investments?**

9 A. Based on the drivers that I discussed above, our capital projects fall into capital  
10 categories depending on the main purpose of the project. These groupings are:

11

12 (1) Transmission Base: This category is primarily for managing the health and  
13 performance of transmission assets. The main goal is to ensure that critical  
14 assets, including transmission lines, substations, and other related assets, meet  
15 reliability and capacity requirements, while minimizing life-cycle costs.

16

17 (2) Reliability Requirement: These are projects that are constructed to ensure that  
18 the Transmission System is compliant with all NERC reliability standards.  
19 Any entity found non-compliant may be subject to fines of up to \$1 million  
20 per day per violation.

21

22 (3) New Business or Customer Need: This category includes projects that we are  
23 required to construct under the FERC Open Access Transmission Tariff  
24 (“OATT”) to accommodate the interconnection requests from generators,  
25 transmission lines, and new load. Investments are often sizeable and  
26 significant to serve these retail and wholesale customers. Investments are  
27 often also planned to support local reliability needs.

28

29 (4) Regional Expansion: This category includes major high-voltage transmission  
30 line projects developed through the regional planning process and seeks to  
31 serve multiple needs, including regional and local reliability and renewable

1 energy outlet. These are multi-year initiatives and the types of projects for  
2 which we seek a CoN and/or Route Permit from the Commission.

3  
4 (5) Other: This category includes transmission facilities that are primarily  
5 generator outlet lines and interconnection facilities. This includes other sole-  
6 use non-network transmission facilities specific to individual customers'  
7 interconnections.

8  
9 Many of Minnesota Power's capital projects serve multiple purposes, but for  
10 budgeting purposes we classify the capital project according to the purpose that  
11 initiated its development. Minnesota Power (Total Company) capital investments in  
12 these projects from 2010 to 2015 (actual), 2016 (forecast), and 2017 (test year  
13 budget) are provided in Exhibit \_\_\_ (CEF), Schedule 1 to my Direct Testimony.

14  
15 **Q. Are some of the projects for which Minnesota Power seeks base rate recovery in  
16 this case previously included in the Company's TCR?**

17 A. Yes. Minnesota Power's proposal for transferring TCR costs to base rates is  
18 discussed in the Direct Testimony of Company witness Herbert Minke. For projects  
19 that are eligible for TCR recovery and are placed in service between December 31,  
20 2016, and December 31, 2017, Minnesota Power will include those in a subsequent  
21 TCR filing and requests that they not be moved into base rates, at this time.

22  
23 **Q. If Mr. Minke is discussing the proposal for transferring rider costs, what is the  
24 purpose of your testimony with respect to transmission project cost recovery?**

25 A. I am providing testimony to explain costs that were incurred to construct these  
26 projects. While the Commission allowed us to recover, within the TCR Rider, our  
27 share of the costs identified in the Commission-approved CoNs, the Commission has  
28 not allowed us to recover, within the rider, costs for construction in excess of those  
29 amounts and other internal labor expenses. To the extent all, or portions of,  
30 transmission project costs were not previously approved for recovery in the TCR, the  
31 Company is now seeking recovery of those amounts in this rate review and is



1 providing justification for those additional costs. I am also providing cost  
2 information for major transmission capital projects that are not TCR-eligible.  
3 Overall, I support base rate recovery of transmission projects placed in service by  
4 December 31, 2017, and not previously included in Minnesota Power's base rates.  
5

6 **1. Transmission Base**

7 **Q. What types of projects are included in transmission base?**

8 A. These projects are typically smaller capital projects done over a shorter period of  
9 time. These smaller projects make up a majority of the total number of projects that  
10 the transmission function completes each year. Transmission Base projects have  
11 traditionally made up only a modest portion of our overall capital budget. Some  
12 examples of these smaller projects include replacement of one or two structures or  
13 cross-arms due to age, condition, or damage. These types of capital projects require  
14 investments in transmission line components, such as poles, conductors, switches,  
15 relays, and land rights for transmission line easements. They also include  
16 investments in substation components such as transformers, capacitor banks, circuit  
17 breakers, remote terminals, communication fiber systems, and real property.  
18

19 This past year, we needed to replace a number of large transformers that are reaching  
20 end-of-life. We are also in the process of replacing two damaged HVDC converter  
21 transformers at the Square Butte Substation facility near Center, North Dakota that  
22 are just over 38 years old. For the last seven years, we have had an on-going program  
23 for replacement of our circuit breakers, investing approximately \$1 million per year.  
24

25 **Q. Why were the 2013 actual investments in transmission base higher than other**  
26 **historic years?**

27 A. Investments in 2013 included almost \$11.0 million dollars in investments in the  
28 HVDC upgrades, which included new bushing replacements for the converter  
29 transformers and replacement for poly-chlorinated biphenyl capacitor banks at the  
30 facility. Additional work included the separation of the Square Butte HVDC facility  
31 from the Minnkota Power Cooperative facility. A new control center was added and

1 the control wiring was migrated into the Minnesota Power HVDC system. These  
2 large capital project investments are often coordinated on a five-year outage cycle  
3 with the Minnkota Power Cooperative Milton R Young facility in Center, North  
4 Dakota.

5  
6 **Q. Are there any major capital investments driving the 2016 forecast or the 2017  
7 budget?**

8 A. Included in the 2016 forecast were transmission projects that are necessary to support  
9 the idling and eventual closure of Minnesota Power's North Shore coal-fired  
10 generation. These projects included those discussed and referenced as the "North  
11 Shore Loop" in my testimony. There were also a significant number of transformers  
12 that experienced "short circuit" faults and required unplanned replacement in 2016.  
13 The 2017 budget has a number of reliability projects driving the T&D budgets for the  
14 next number of years. For example, the Company has budgeted \$4.4 million dollars  
15 for the 15 Line 115 kV transmission line replacement. This is a three-year project  
16 that will require many of the current structures to be replaced and the entire line to be  
17 reconducted. However, the most significant capital project for 2016 and 2017 is the  
18 GNTL, which will begin construction in late 2016 or early 2017.

19  
20 **2. Reliability Requirement**

21 a. Badoura 115 kV Transmission Project

22 **Q. Please describe the Badoura 115 kV Transmission Project ("Badoura Project").**

23 A. The Badoura Project was certified by the Commission in 2006 in Docket No.  
24 ET2,E015/TL-05-867, under the biennial transmission planning process established in  
25 Minn. Stat. § 216B.2425 and Minn. R. ch. 7848. This effort was a joint project  
26 between Minnesota Power and Great River Energy with ownership divided by  
27 segments.

28  
29 The Badoura Project consists of approximately 63 miles of overhead 115 kV  
30 transmission line and associated substation modifications between the endpoints of  
31 Pequot Lakes, Pine River, Badoura, Hackensack, and Park Rapids. The project

1 connects the Pequot Lakes Substation, located northeast of Pequot Lakes, a new Pine  
2 River Substation, located southwest of Pine River, the Badoura Substation, the Birch  
3 Lake Substation, located east of Hackensack, and the Long Lake Substation, located  
4 east of Park Rapids, all in Minnesota.  
5

6 **Q. What segments of the Badoura Project does Minnesota Power own?**

7 A. Minnesota Power owns two transmission segments, the Pequot Lakes Substation to  
8 Pine River Substation 9-mile, 115 kV transmission line and the Pine River Substation  
9 to Badoura Substation 21-mile, 115 kV transmission line. Minnesota Power also  
10 owns the Pequot Lakes Substation, the Badoura Substation, and the new Pine River  
11 115kV/34.5 kV Substation.  
12

13 **Q. Why was the Badoura Project needed?**

14 A. Load growth in the Park Rapids area has resulted in a considerable increase in  
15 electrical use in the region. The historic transmission and distribution systems were  
16 not adequate to support voltage within acceptable levels based on projected load  
17 growth rates without the addition of the Badoura Project. Minnesota Power's and  
18 Great River Energy's customers in the Park Rapids and surrounding area now benefit  
19 from the addition of the 115 kV transmission line and associated substation upgrades.  
20

21 **Q. What was the initial estimate for the total Badoura Project?**

22 A. The total Badoura Project was estimated to cost between \$36.3 million and \$42.3  
23 million in 2007 dollars, without AFUDC or internal costs.  
24

25 **Q. What is Minnesota Power's share of the total Badoura Project cost estimate?**

26 A. Minnesota Power's share of the total project cost was estimated to come in at or  
27 below \$22 million, in 2007 dollars. In 2008, Minnesota Power updated its cost  
28 estimate to \$23.35 million (Docket No. E015/M-08-1176), in 2009 dollars, to include  
29 price increases in structural steel and transformer prices for the Pine River Substation  
30 (\$350,000 increase), a revised layout for the Badoura Substation (from a single bus  
31 design with a tie breaker to a ring bus design) (\$1.0 million increase), and an increase

1 in commodity prices related to structural steel and transformers (\$1.0 million  
 2 increase). These cost increases were partially offset by a decrease in the amount  
 3 spent on preconstruction activities (\$1.0 million reduction).

4  
 5 **Q. What did it cost Minnesota Power to construct the Badoura Project?**

6 A. Minnesota Power spent \$22.21 million to construct its segments of the Badoura  
 7 Project. This amount includes all the sales tax credits that were credited to the project  
 8 in 2011 to 2013. A table summarizing initial estimates (without AFUDC or internal  
 9 costs) and final costs (with AFUDC and internal costs) is provided in Table 1.

10  
 11  
 12 **Table 1**  
**Badoura 115 kV Transmission Project<sup>+</sup>**  
**(Dollars in Millions)**

Project Description	Project Estimate	Updated Project Estimate	Actual Total Project Cost <sup>6</sup>	Actual Total Project Costs (Adjusted) <sup>#</sup>
Badoura Project	\$22.00	\$23.35 <sup>7</sup>	\$22.21 <sup>8</sup>	\$20.7
Dates (Relevant)	2007	2008	2007-2011	2007
+ MPUC Docket No. ET2,E015/TL-05-867				
# Handy-Whitman is used to determine the de-escalated costs back to dates of project estimates.				

11

12 **Q. Are any costs for the Badoura Project included in Minnesota Power’s TCR or in**  
 13 **current base rates?**

14 A. Yes. As part of Minnesota Power’s 2009 rate review, the portions of the Badoura  
 15 Project that had been completed and placed in service (\$17.72 million) were included  
 16 in base rates. In Minnesota Power’s 2010 TCR docket, Docket No. E015/M-10-799,

<sup>6</sup> \$17.72 million in costs for the Badoura Project were placed in base rates at the conclusion of Minnesota Power’s 2009 rate review. At this time, Minnesota Power is requesting to move approximately \$4.49 million in Badoura Project costs from the TCR to base rates so that all costs associated with this project are in base rates.

<sup>7</sup> The updated project cost approved in Docket No. E015/M-08-1176 for the Badoura Project was provided in nominal dollars.

<sup>8</sup> The Company’s Response to Department Information Request No. 3 provided as Attachment 3 to the Department of Commerce’s (“Department”) August 20, 2014, Comments in Docket No. E015/M-14-337 supports this number. In Docket No. E015/M-14-337, the Company inadvertently included a typo indicating that the final cost of the Badoura Project was \$22.2 million. As stated in the Company’s TCR filing in 2011 (Docket No. E015/M-11-695) on page 19 of the Petition, the fully in-service project cost for the Badoura Project is \$22,918,728 (prior to the subsequent sales tax credits from 2011 to 2013).

1 the Commission approved inclusion of on-going expenses related to the three  
2 remaining portions of the Badoura Project, excluding internal capitalized costs.

3

4 **Q. When was the Badoura Project placed in service?**

5 A. The first portion of the Badoura Project was placed in service in 2009. The three  
6 remaining project segments were placed in service in 2011.

7

8 **Q. Did Minnesota Power prudently incur the costs it spent to complete the Badoura  
9 Project?**

10 A. Yes. The costs incurred by the Company to complete the Badoura Project were  
11 prudently and reasonably incurred to complete this necessary project, and the  
12 majority were previously approved for cost recovery. In this Docket, Minnesota  
13 Power requests that the Badoura Project costs currently being collected in the TCR, as  
14 well as all internal labor and costs that were previously excluded for cost recovery  
15 through the TCR, be included in Minnesota Power base rates and recovered in full.

16

17 b. Savanna 115 kV Transmission Project

18 **Q. Please describe the Savanna 115 kV Transmission Project (“Savanna Project”).**

19 A. The Savanna Project was approved by the Commission in Docket Nos.  
20 ET2,E015/CN-10-973 and ET2,E015/TL-10-1307. This project was a joint project  
21 between Minnesota Power and Great River Energy with ownership divided by  
22 segments. Minnesota Power is the sole owner of the new Savanna 115 kV Switching  
23 Station near Floodwood, Minnesota, and the upgrades to the Minnesota Power 9 Line,  
24 between the Savanna Switching Station and the Floodwood Tap (“9 Line Tap  
25 Upgrades”).

26

27 **Q. When was the Savanna Project placed in service?**

28 A. The Savanna Switching Station and two related 115 kV line extension projects were  
29 placed in service in 2013. The 9 Line Tap Upgrades could not be constructed until  
30 Great River Energy completed construction of its main segment of the project, a new

1 Savanna – Cromwell 115 kV Line. The 9 Line Tap Upgrades will be completed and  
2 in-service prior to the end of 2016.

3

4 **Q. What was the initial estimate for the total Savanna Project?**

5 A. The Savanna Project was estimated to cost \$29 million, in 2010 dollars.

6

7 **Q. What is Minnesota Power’s share of the total Savanna Project cost estimate?**

8 A. Minnesota Power’s share of the total project cost was estimated to come in at or  
9 below \$4.1 million, in 2010 dollars, without AFUDC or internal costs.

10

11 **Q. What did it cost Minnesota Power to construct the Savanna Project?**

12 A. Minnesota Power spent \$5.08 million, in nominal dollars, to construct its segments of  
13 the Savanna Project between the years 2012 and budgeted 2016. Using the Handy-  
14 Whitman Indices to account for inflation, the Savanna Project costs are equivalent to  
15 \$4.72 million in 2010 dollars, approximately \$0.62 million above the original  
16 estimate of \$4.10 million in 2010 dollars. The original estimate and final costs are  
17 summarized in Table 2.

18

**Table 2<sup>9</sup>**  
**Savanna 115 kV Transmission Project<sup>+</sup>**  
**(Dollars in Millions)**

<b>Project Description</b>	<b>CoN Project Estimate</b>	<b>Route Permit Project Estimate</b>	<b>Actual Total Project Cost</b>	<b>Actual Total Project Costs (Adjusted)<sup>#</sup></b>
Savanna Project	\$4.10	N/A	\$5.08	\$4.72
Dates (Relevant)	2010		2012-2016	2010
<b># Handy-Whitman is used to determine the de-escalated costs back to dates of project estimates.</b>				
<b>+ MPUC Docket No. ET2,E015/CN-10-973 and ET2,E015/TL-10-1307</b>				

19

20 **Q. What contributed to the variance?**

21 A. Following acquisition of the CoN and Route Permit for the Savanna Project, and  
22 during the engineering phase of the project, the Company identified that it would

<sup>9</sup> Actual Total Project Cost includes the amount forecasted to be spent in 2016.

1 incur additional switching station costs. Specifically, the initial estimate provided in  
2 the application inadvertently excluded labor costs.

3

4 However, the primary reasons for the cost increase can be attributed to the  
5 development of a more detailed estimate for the switching station and unanticipated  
6 magnitude of geographical challenges associated with the switching station site.

7

8 **Q. Please explain how challenges encountered during construction of the Savanna  
9 Project contributed to additional costs.**

10 A. Construction of the switching station was found to be more challenging than  
11 originally anticipated. Prior to development of the Savanna Project, the Floodwood  
12 area was served by a single 115 kV line. The Savanna Switching Station was  
13 constructed and interconnected to this 115 kV line. With no redundant connection at  
14 the time, construction of the switching station had to be staged so as to minimize  
15 interruption to the Floodwood-area customers served from the single 115 kV line.  
16 This resulted in several intermediate steps and a need for live line work that are not  
17 typical for new construction and are more expensive.

18

19 The construction of the Savanna – Cromwell 115 kV Line by Great River Energy –  
20 which could not be completed until the Savanna Switching Station was constructed –  
21 has alleviated these concerns in the Floodwood area for the foreseeable future. In  
22 addition to the complexity of construction at the switching station site, the site itself  
23 was found to be much wetter than anticipated. This led to site access and  
24 development costs in excess of what would be typical for a site with less extensive  
25 wetland characteristics.

26

27 **Q. Can you provide a breakdown of the cost increases for the Savanna Project?**

28 A. Yes. The quantifiable cost increases associated with the Savanna Project construction  
29 are summarized in Table 3. The original estimate did not include AFUDC or  
30 overheads that get assigned to every completed project. I have identified these

1 quantifiable amounts, which are included in the forecasted cost of \$5.08 million, in  
2 this table.

3

**Table 3**  
**Savanna Cost Summary**

<b>Cost Driver</b>	<b>Estimated Cost Impact</b>
Construction in wet conditions (matting)	\$87,000
Labor costs not included in estimate	\$500,000
Equipment not included in estimate	\$81,000
Project indirect charges (AFUDC, Company overheads)	\$316,000

4

5 **Q. Were any costs for the Savanna Project included in Minnesota Power’s TCR?**

6 A. Yes. Minnesota Power included \$4.31 million (with AFUDC), the amount spent  
7 through 2014, in its TCR. This amount was spent to complete three of the four  
8 projects for which Minnesota Power was responsible. After de-escalating to 2010  
9 dollars, this amount was under the CoN estimate.

10

11 **Q. Did Minnesota Power prudently incur the costs it spent to complete the Savanna**  
12 **Project?**

13 A. Yes. The costs incurred by the Company to complete the Savanna Project were  
14 prudently and reasonably incurred to complete this necessary project.

15

16 **Q. What does the Company request the Commission do with the costs for the**  
17 **Savanna Project?**

18 A. Minnesota Power requests that the Commission allow the Company to recover the  
19 Savanna Project costs in base rates.

20

21 c. Deer River 115 kV Transmission Project

22 **Q. What is the Deer River 115 kV Transmission Project (“Deer River Project”)?**

23

A. The Deer River Project includes:



- 1 • Construction of a new 1-mile 115 kV transmission line from an existing 115
- 2 kV transmission line north of US Highway 2 and terminating at an existing
- 3 transmission line outside the Enbridge Deer River electrical substation;
- 4 • Construction of a new 0.3-mile double-circuit 230 kV transmission line
- 5 between the existing 230 kV transmission line south of US Highway 2 and the
- 6 proposed Zemple Substation;
- 7 • Removal of Minnesota Power’s existing Deer River 115 kV/23 kV Substation
- 8 and replacement with a new Minnesota Power Zemple 230 kV/115 kV/23 kV
- 9 Substation in the same location; and
- 10 • Removal of an existing 7.5-mile 115 kV transmission line.

11

12 **Q. Was a CoN obtained for the Deer River Project?**

13 A. No, because the Deer River Project did not meet the statutory threshold criterion

14 requirements for the CoN as set forth in Minn. Stat. § 216B.243 and Minn. R. ch.

15 7849; therefore, a CoN was not required (or petitioned) for the Deer River Project.

16 However, Minnesota Power obtained a Route Permit for the Deer River Project from

17 the Commission in Docket No. E015/TL-13-68.

18

19 **Q. Why was the Deer River Project needed?**

20 A. Prior to construction of the Deer River Project, the Deer River area was served by a

21 single 7.5-mile-long, 115 kV line (“Deer River Tap”). The Deer River Tap was a

22 direct extension from a larger 30-mile 115 kV line connecting the Boswell Substation

23 and the Nashwauk Substation (“28 Line”). The Deer River Project was necessary to

24 address several issues with this configuration.

25

26 **Q. What issues did the Deer River Project address?**

27 A. There were four specific issues the project addressed: (1) limited capacity on the Deer

28 River Tap to serve multiple load-serving substations, including the Great River

29 Energy Cohasset Substation, the Minnesota Power Deer River 115/23 kV Substation,

30 the Great River Energy Deer River 115 kV/69 kV Substation, and three additional

31 substations that serve a single Enbridge pumping station facility (“Enbridge Deer

1 River Pump Station”); (2) limited capacity on the Deer River Tap to support a  
2 planned expansion resulting in a significant increase in load requirements at the  
3 Enbridge Deer River Pump Station; (3) difficulty associated with maintenance or  
4 upgrade of the Deer River Tap due to the single-source arrangement of the system in  
5 the Deer River area and outage restrictions associated with the Enbridge Deer River  
6 Pump Station (in most cases, maintenance or upgrades would have to be done, at least  
7 in part, while the line was energized in order to minimize disruption to customers in  
8 the Deer River area); and (4) the number of load-serving taps and the total amount of  
9 load served from the larger Boswell – Nashwauk 115 kV Line, which exceeded  
10 Minnesota Power’s criteria of three total taps or 30 MW of total load.

11  
12 As an alternative to rebuilding the Deer River tap and terminating it at the Boswell  
13 Substation, the Zemple 230 kV/115 kV Substation provides significantly improved  
14 reliability, redundancy, constructability, and long-term load-serving capability for the  
15 Deer River area. Customers in the Deer River area are no longer subject to outages  
16 anywhere along the 30-mile Boswell – Nashwauk 115 kV Line, and customers served  
17 from the Boswell – Nashwauk 115 kV Line are no longer subject to outages on the  
18 Deer River Tap. The parallel development of a 115 kV line between Great River  
19 Energy’s Deer River 115 kV/69 kV Substation and the Enbridge Deer River Pump  
20 Station further enhanced Minnesota Power’s ability to build the Zemple Substation  
21 and operate and maintain the transmission system in the Deer River area for the  
22 foreseeable future.

23  
24 **Q. What was Minnesota Power’s cost estimate for the Deer River Project at the**  
25 **time the Route Permit was obtained?**

26 A. Minnesota Power estimated the Deer River Project would cost \$13.82 million  
27 (without AFUDC and indirect overheads), in 2013 dollars.

28  
29 **Q. What is the current estimate for the total cost of the Deer River Project?**

30 A. While the project has not yet been completed, Minnesota Power’s current estimate for  
31 the complete Deer River Project is \$16.65 million in nominal dollars, including actual

1 costs from 2012 to 2015, forecasted costs in 2016, and the budget expenses for 2017.  
 2 Using the Handy-Whitman Indices to account for inflation, the Deer River Project  
 3 costs are equivalent to \$16.15 million in 2013 dollars, approximately \$2.33 million  
 4 above the original estimate of \$13.82 million in 2013 dollars. Original estimates and  
 5 final costs are summarized in Table 4.  
 6

**Table 4<sup>10</sup>**  
**Deer River 115 kV Transmission Project<sup>+</sup>**  
**(Dollars in Millions)**

<b>Project Description</b>	<b>CoN Project Estimate</b>	<b>Route Permit Project Estimate</b>	<b>Actual Total Project Cost</b>	<b>Actual Total Project Costs (Adjusted)<sup>#</sup></b>
Deer River Project	N/A	\$13.82	\$16.65	\$16.15
Dates (Relevant)	N/A	2013	2012-2017	2013
<sup>#</sup> Handy-Whitman is used to determine the de-escalated costs back to dates of project estimates.				
<sup>+</sup> MPUC Docket No. E015/TL-13-68				

7

8 **Q. Are any costs associated with the Deer River Project included in the TCR?**

9 A. No. Although Minnesota Power requested that this project be included in the TCR in  
 10 Docket No. E015/M-15-472, the Commission denied recovery in the rider because  
 11 the project did not obtain a CoN and also did not meet one of the CoN exemptions  
 12 specified in Minn. Stat. § 216B.243, subd. 8.  
 13

14 **Q. Why are the Deer River Project costs higher than estimated in the route permit proceeding?**

15  
 16 A. The primary cost drivers associated with the higher Deer River Project costs relate to  
 17 the construction of the Zemple Substation and the 230 kV transmission line. The  
 18 Company did not include project indirect costs (e.g., AFUDC, overheads, and  
 19 allocations, etc.) in the Route Permit estimate. The construction of the Zemple  
 20 Substation was challenged by site soil conditions and the need for additional,  
 21 unanticipated, sub-grade work. The construction of the 230 kV transmission line was  
 22 more costly than initially estimated due to the need to complete 230 kV line

---

<sup>10</sup> Actual total Project Cost includes the amount forecasted to be spent in 2016 and budgeted for 2017.

1 construction while the existing transmission lines were energized; the estimate did not  
 2 consider this more complicated work condition. Also, easement acquisition costs  
 3 were higher than initial estimates. Construction of the 230 kV line also required  
 4 substantial matting during construction to protect existing pipeline infrastructure in  
 5 the area. Costs for the removal of the 7.5 miles of 115 kV transmission line were also  
 6 higher than anticipated due to access point concerns, county road crossing costs, and  
 7 the need to mat over existing pipelines in the easement. These costs are summarized  
 8 in Table 5.

9  
 10 **Table 5**  
 11 **Deer River Project Cost Summary**

Cost Driver	Estimated Cost Impact
Access considerations and matting for 115 kV line removal	\$390,000
Electrical equipment enclosure for Zemple Substation	\$500,000
Hot-work, matting, and redesign of 230 kV line due to substation layout change	\$400,000
Substation sub-grade correction	\$300,000
Minnesota Power project cost indirect (overheads & AFUDC)	\$700,000

12  
 13 **Q. Did Minnesota Power prudently incur the costs it spent to complete the Deer**  
 14 **River Project?**

15 A. Yes. The costs incurred by the Company to complete the Deer River Project were  
 16 prudently and reasonably incurred to complete this necessary project. Although final  
 17 construction costs for the Deer River Project are higher than the original estimate, the  
 18 Company mitigated costs by completing construction of the 115 kV transmission line  
 19 more cost-efficiently than originally estimated.

20  
 21 **Q. What does the Company request the Commission do with the costs for the Deer**  
 22 **River Project?**

23 A. Minnesota Power requests that the Commission allow the Company to recover the  
 24 Deer River Project costs of \$16.65 million (with AFUDC and Company indirect  
 25 overheads and allocations) in base rates.

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31

d. Straight River 115 kV Transmission Project

**Q. What is the Straight River 115 kV Transmission Project (“Straight River Project”)?**

A. The Straight River Project includes the construction of the new Straight River 115 kV/34.5 kV Substation, a 115 kV transmission line tap to serve the Straight River Substation from the new Great River Energy Hubbard – Blueberry 115 kV Line, and a new 34.5 kV distribution feeder from Straight River to the existing Minnesota Pipeline Park Rapids Pumping Station, all located in Hubbard County, Minnesota. The Straight River Project is part of a larger collaborate project undertaken by Great River Energy and Minnesota Power known as the “Menahga Area 115 kV Project.” Great River Energy and Minnesota Power were granted a CoN and Route Permit for the Menahga Area 115 kV Project from the Commission in Docket Nos. ET2,E015/CN-14-787 and ET2,E015/TL-14-797, respectively.

**Q. Why was the Straight River Project needed?**

A. As a component of the larger Menahga Area 115 kV Project, the Straight River Project contributes to the resolution of two parallel load-serving needs. The Menahga Area 115 kV Project was designed to resolve load-serving issues, including transformer and feeder capacity limitations, on the 34.5 kV distribution system used jointly by Minnesota Power and Great River Energy to serve customers in the areas between the Hubbard and Verndale substations. Communities in the geographical area that benefits from the project include Menahga, Nimrod, Sebeka, Verndale, and the areas between. In particular, the Straight River Project moves a substantial industrial load (a pipeline pumping station) onto an independent source, improving power quality for the customers served from the Hubbard – Verndale 34.5 kV system and contributing to the alleviation of capacity constraints on the system. The second load-serving need satisfied by the Menahga Area 115 kV Project involved the extension of electric service by Great River Energy and Todd-Wadena Electric Cooperative to a new Koch Pipeline pumping station near Sebeka, Minnesota.

1 **Q. What was Minnesota Power’s cost estimate for the Straight River Project at the**  
2 **time the combined CoN and Route Permit was obtained?**

3 A. Minnesota Power estimated the Straight River Project would cost \$2.81 million, in  
4 2014 dollars. Unlike earlier projects, the Straight River Project estimate included all  
5 the AFUDC and Company overheads in the CoN and Route Permit estimate.  
6

7 **Q. Are any Straight River Project costs included in the TCR?**

8 A. No.  
9

10 **Q. What was the final cost of the Straight River Project?**

11 A. While the Project has not yet been completed, it will be placed in service in 2016.  
12 Minnesota Power’s current estimate for the Straight River Project is \$2.51 million  
13 dollars. This project is expected to be completed below the project estimate provided  
14 in the CoN. The CoN cost estimate and expected final cost for the Straight River  
15 Project are summarized in Table 6.  
16

**Table 6<sup>11</sup>**  
**Straight River 115 kV Transmission Project<sup>+</sup>**  
**(Dollars in Millions)**

<b>Project Description</b>	<b>CoN Project Estimate</b>	<b>Route Permit Project Estimate</b>	<b>Actual Total Project Cost (Nominal)</b>
Straight River Project	\$2.81	\$2.81	\$2.51
Dates (Relevant)	2014	2014	2014-2016
+ MPUC Docket No. E015/CN-14-787 and E015/TL-14-797			

17  
18 **Q. Why are the actual costs for the Straight River Project expected to be less than**  
19 **the estimates in the CoN?**

20 A. Contract labor and materials were less than anticipated on the substation. In addition,  
21 the 57L tap line construction, from Great River Energy, had lower contract labor and  
22 material costs than anticipated. These are summarized in Table 7.  
23

<sup>11</sup> Actual Total Project Cost includes the amount forecasted to be spent in 2016.

1  
2

**Table 7**  
**Straight River Project Cost Summary**

<b>Cost Driver</b>	<b>Estimated Cost Impact</b>
Lower contract labor and materials expenses for substation	(\$200,000)
Lower contract labor and materials expenses for line construction	(\$100,000)

3

4 **Q. Did Minnesota Power prudently incur the costs it spent to complete the Straight**  
5 **River Project?**

6 A. Yes. The costs incurred by the Company to complete the Straight River Project were  
7 prudently and reasonably incurred to complete this necessary project.

8

9 **Q. What does the Company request the Commission do with the costs for the**  
10 **Straight River Project?**

11 A. Minnesota Power requests that the Commission allow the Company to recover the  
12 Straight River Project costs in base rates.

13

14 e. NERC Required Projects

15 **Q. What are the “NERC Required Projects” as defined in this part of your**  
16 **testimony?**

17 A. These are transmission upgrade projects made in response to NERC’s October 7,  
18 2010, Recommendation to Industry for Consideration of Actual Field Conditions in  
19 Determination of Facility Ratings (“NERC Recommendation”).

20

21 **Q. What is a NERC recommendation?**

22 A. NERC’s role includes discovering, identifying, and providing information that is  
23 critical to ensuring the reliability of the bulk power system in North America. To  
24 effectively disseminate this information, NERC utilizes e-mail-based “alerts”  
25 designed to provide concise, actionable information to the electricity industry. NERC  
26 alerts are divided into three levels:

- 27 • Industry Advisory – Purely informational and intended to alert registered  
28 entities to issues or potential problems. A response to NERC is not necessary.

- 1 • Recommendation to Industry – Recommended specific action be taken by  
2 registered entities. Requires a response from recipients as defined in the alert.
- 3 • Essential Action – Identify actions deemed to be essential to bulk power  
4 system reliability. Requires NERC Board of Trustees approval prior to  
5 issuance. Essential actions also require recipients to respond as defined in the  
6 alert.

7

8 **Q. Why did NERC issue the October 7, 2010, NERC Recommendation?**

9 A. According to the information provided in the NERC Recommendation, it was issued  
10 because NERC and its regional entities had become aware of discrepancies between  
11 design and actual field conditions of transmission facilities. NERC believed that  
12 these deficiencies were significant and widespread, with the potential to result in  
13 facility ratings that were inconsistent with actual field conditions. All recipients of  
14 the NERC Recommendation were required to respond.

15

16 **Q. Did NERC identify how it became aware of these potential issues?**

17 A. Information in the NERC Recommendation indicates that the issues were identified  
18 from the root cause analysis for a transmission owner’s conductor-to-ground fault  
19 caused by a vegetation contact with a transmission line. Subsequent evaluation of the  
20 condition of the line indicated that the conductor-to-ground clearance of the line was  
21 less than expected. In response, the transmission owner contracted with a company  
22 that uses Light Detection and Ranging (“LiDAR”) and Power Line Systems –  
23 Computer Aided Design and Drafting (“PLS-CADD”) technologies to survey and  
24 model additional of its transmission lines.

25

26 Using these technologies, the transmission owner identified a large number of  
27 additional previously-undetected instances in which the conductor-to-ground  
28 clearance of a transmission line was less than expected. Because transmission line  
29 ratings are most often limited by conductor-to-ground clearance, the identified  
30 clearance discrepancies resulted in the need to adjust the facility ratings of many of



1 the transmission owner's transmission lines until modifications could be implemented  
2 to restore the necessary conductor-to-ground clearance.

3  
4 **Q. What is the result of needing to modify conductor ratings like that transmission**  
5 **owner was required to do?**

6 A. Derating (reducing the operational capacity of) a transmission line has the effect of  
7 operationally limiting the conductor's ability to transmit electricity.

8  
9 **Q. What process did Minnesota Power undertake to complete the assessment**  
10 **required by the NERC Recommendation?**

11 A. Minnesota Power was required to review the current facility ratings methodology for  
12 all transmission lines to verify that the methodology used to determine facility ratings  
13 is based on actual field conditions. Transmission line facility ratings depend on many  
14 limiting factors, including transmission facility placement, tower height,  
15 topographical profiles, and maintaining adequate conductor clearances (i.e.,  
16 conductor-to-ground, conductor-to-conductor) under a variety of ambient weather and  
17 loading conditions.

18  
19 The Company had to describe plans to complete an assessment of our transmission  
20 facilities to verify whether the actual field conditions conform to the entity's design  
21 tolerances in accordance with its facility ratings methodology and to describe how  
22 and when all transmission lines will be assessed. All transmission owners were  
23 required to provide this information to NERC.

24  
25 Within six months of the date of the NERC Recommendation, each registered entity  
26 was to have identified and reported to the applicable reliability coordinators and  
27 regional entities all transmission facilities where an entity determined that the actual  
28 field conditions were different than the design condition of the facilities and what  
29 those differences were. Each registered entity was to correct any issues identified in  
30 its assessment no later than October 7, 2012.

31

1 **Q. Did NERC make any modifications to this deadline?**

2 A. Based on feedback from the registered entities, NERC reconsidered the complexity of  
3 this task and modified the timeline for identification of facilities for which actual field  
4 conditions may impact line ratings and necessitate mitigation. Discrepancies for the  
5 highest-priority facilities with regard to bulk power system reliability were to be  
6 identified and reported to the applicable regional entity no later than December 31,  
7 2011, medium-priority facilities were to be reported no later than December 31, 2012,  
8 lowest-priority facilities were to be reported no later than December 31, 2013. Any  
9 discrepancies identified in the course of the evaluation were to be mitigated within  
10 one year. Due to the volume of discrepancies identified on Minnesota Power's  
11 transmission lines, Minnesota Power subsequently requested, and was granted  
12 extensions, for its medium-priority and low-priority facilities to June 30, 2014, and  
13 December 31, 2016, respectively.

14

15 **Q. Does this mean Minnesota Power was not adequately maintaining its**  
16 **Transmission System?**

17 A. No. This is more reflective of the age of Minnesota Power's Transmission System.  
18 While the transmission facilities were well-designed and well-built, with many  
19 serving customers beyond the depreciated lives, eventually additional maintenance is  
20 necessary.

21

22 **Q. Describe the process Minnesota Power undertook to prioritize and complete**  
23 **these upgrades in response to the NERC requirement.**

24 A. Minnesota Power's assessment plan for the NERC Recommendation involved  
25 evaluating each of its transmission lines as follows:

26 (1) Transmission lines built or upgraded in the five years immediately prior to the  
27 date of the original NERC Recommendation were reported to the regional  
28 entity on July 15, 2011, and excluded from the assessment.

29

30 (2) The rest of Minnesota Power's transmission lines were analyzed using new  
31 PLS-CADD models developed from aerial LiDAR surveys acquired

1 specifically for the NERC Recommendation assessment. The PLS-CADD  
2 models were used to identify ratings discrepancies and, when required, to  
3 develop mitigation measures.  
4

5 **Q. What kinds of upgrades were made to Minnesota Power’s transmission lines to**  
6 **comply with the NERC requirement?**

7 A. Broadly speaking, all identified discrepancies were either addressed by derating of the  
8 facility or through some sort of physical modification of the transmission line or the  
9 surrounding environment.  
10

11 Minnesota Power used line derating where possible, and 157 potential discrepancies  
12 on 7 medium priority lines were mitigated without requiring physical construction.  
13 Physical mitigation was required for 239 actual discrepancies on 18 medium priority  
14 (230 kV and +/- 250 kV HVDC) lines. This generally consisted of installing a  
15 transmission structure to increase conductor-to-ground clearances. In some instances,  
16 other mitigation methods, such as burying or lowering a distribution line or removing  
17 an object in the right-of-way, were also utilized.  
18

19 Minnesota Power used line derating on 761 of the total 1,689 low priority (115 kV,  
20 138 kV, and 161 kV) spans of interest and did not require physical construction. In  
21 our July 15, 2016, update to the Midwest Reliability Organization (“MRO”),  
22 Minnesota Power reported that 815 of the remaining 928 discrepancies had been  
23 physically mitigated. The vast majority of discrepancies were mitigated by installing  
24 or replacing transmission structures to increase conductor-to-ground clearances.  
25

26 **Q. Were any of these NERC Required Project costs included in any of Minnesota**  
27 **Power’s retail rate riders?**

28 A. No.  
29

1 **Q. When were the NERC Required Projects completed?**

2 A. Minnesota Power successfully completed the mitigation of all discrepancies on its  
3 medium-priority lines on June 24, 2014. While mitigation of discrepancies on low-  
4 priority lines is ongoing, 815 of the 928 total discrepancies requiring physical  
5 mitigation had been mitigated prior to July 15, 2016. Construction on the remaining  
6 discrepancies will continue through the rest of 2016, with mitigation of all  
7 discrepancies on low priority facilities anticipated to be complete by December 31,  
8 2016.

9  
10 **Q. What are the total estimated costs of this effort for the NERC Required  
11 Projects?**

12 A. The total cost was originally estimated at between \$75 and \$85 million dollars. This  
13 was based on an estimated mitigation cost per discrepancy. Specific information for  
14 the transmission lines became available as our consultant completed the flights and  
15 was able to process the data and model the transmission lines. The Company refined  
16 its estimate to \$68.6 million through December 31, 2016. However, the Company  
17 has been able to take advantage of construction and access efficiencies as it has  
18 worked through the physical modifications. The Company anticipates that final  
19 project costs may come in below the \$10.25 million amount originally forecasted to  
20 be spent in 2016, and below the overall forecasted project total of \$68.63 million.

21  
22 **Q. Is Minnesota Power proposing to include costs associated with the NERC  
23 Required Projects in base rates?**

24 A. Yes, Minnesota Power is proposing to include all costs associated with the projects in  
25 service by December 31, 2016, in base rates.

26  
27 **Q. What steps did Minnesota Power take to control costs associated with the NERC  
28 Required Projects?**

29 A. Minnesota Power worked to control costs associated with the NERC Required  
30 Projects by streamlining its assessment of transmission lines, by requesting deadline

1 extensions from the MRO, and through various construction and contracting  
2 considerations.

3  
4 Part of Minnesota Power's assessment plan included identifying a minimum-required  
5 rating for each of its transmission lines. Analysis was conducted to identify the  
6 anticipated power flow on each transmission facility under a variety of limiting  
7 conditions, and a minimum required rating was recommended to provide sufficient  
8 capability for all evaluated scenarios. This allowed for the targeted ratings of many  
9 of Minnesota Power's transmission lines to be reduced while retaining a reasonable  
10 degree of confidence that sufficient capacity would be available barring a significant  
11 change in circumstances. Reducing the targeted ratings of these transmission lines  
12 significantly decreased the overall cost of the NERC Required Projects by limiting  
13 physical construction.

14  
15 Given the accuracy of the LiDAR-based PLS-CADD line models developed in  
16 response to the NERC Recommendation, smaller design margins could be applied to  
17 the required clearances when performing the necessary evaluation. This reduction in  
18 clearance margins through the use of more accurate LiDAR-based models resulted in  
19 a higher degree of certainty in the identification of these discrepancies and fewer  
20 overall discrepancies than what would have been identified using traditional methods,  
21 leading to a further reduction in the total number of limiting spans requiring field  
22 mitigation.

23  
24 **Q. How did requesting deadline extensions control costs?**

25 A. The total number of discrepancies identified on Minnesota Power's transmission  
26 lines, coupled with outage limitations and a need for seasonal construction in the vast  
27 wetland areas of northern Minnesota, made meeting the deadlines mandated by the  
28 NERC Recommendation very challenging. Rather than paying a premium for  
29 transmission service in an attempt to meet the NERC Recommendation deadlines,  
30 Minnesota Power twice submitted extension requests to the MRO to allow  
31 construction to continue on a more reasonable and cost-effective timeline.

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30

**Q. Did Minnesota Power prudently incur the costs it spent to complete the NERC Reliability Projects**

A. Yes. The costs incurred by the Company to complete the NERC Reliability Projects were prudently and reasonably incurred to complete this necessary project.

**Q. What does the Company request the Commission do with the costs for the NERC Reliability Projects?**

A. Minnesota Power requests that the Commission allow the Company to recover the NERC Reliability Projects cost in base rates.

f. North Shore Loop

**Q. Are there any other large transmission projects that will go into service in 2016 and 2017 that you would like to discuss?**

A. Yes. Several projects associated with a multi-year transmission plan for the North Shore Loop (“North Shore Loop Plan”) will be placed in service in 2016 and 2017. Work on additional North Shore Loop Plan projects is expected to continue through at least 2020.

**Q. What is the North Shore Loop?**

A. The North Shore Loop refers to an approximately 140-mile portion of 115 kV and 138 kV transmission lines in the northeastern Minnesota transmission system. The North Shore Loop extends approximately 70 miles along the North Shore of Lake Superior from east Duluth to the Taconite Harbor Energy Center near Schroeder, then turns west and extends approximately another 70 miles, to the Laskin Energy Center near Hoyt Lakes. The North Shore Loop is used by Minnesota Power and Great River Energy to serve customers along the North Shore of Lake Superior and in the Hoyt Lakes area. A figure showing the system is provided in Exhibit \_\_\_ (CEF), Schedule 2.

1 **Q. What generating assets support the North Shore Loop?**

2 A. The Laskin Energy Center, Taconite Harbor Energy Center, and Silver Bay  
3 generating assets provide important sources of power and voltage support to maintain  
4 system reliability along the North Shore Loop. The two generators at Laskin Energy  
5 Center and the two generators at Taconite Harbor Energy Center are owned by  
6 Minnesota Power, while the two generators at Silver Bay are owned by Silver Bay  
7 Power Company, a subsidiary of Cliffs Natural Resources Inc.

8

9 **Q. Why are significant transmission improvements in this area necessary?**

10 A. All seven of the coal-fired generators at these stations have been or will be converted  
11 to peaking operation, idled, or retired over a span of approximately five years for  
12 various reasons. In 2015, the two generators at Laskin Energy Center were converted  
13 from coal-fired baseload generators to natural gas peaking units. Also in 2015,  
14 Minnesota Power retired one of the generators at Taconite Harbor.<sup>12</sup> With  
15 Commission approval in the 2015 Integrated Resource Plan, Minnesota Power idled  
16 the other two units in the fall of 2016 with all coal-fired operations to cease at the  
17 facility by 2020.<sup>13</sup> In June 2016, Silver Bay Power Company idled one of the Silver  
18 Bay generators and has stated its intention to idle the second unit by the end of 2019.  
19 This transition away from local coal-fired baseload generation in the North Shore  
20 Loop has necessitated an evaluation of the transmission system in the area to ensure  
21 that it may be operated reliably and with sufficient load-serving capacity without the  
22 power and voltage support previously provided by the generators. While this  
23 evaluation is presently ongoing, it has already resulted in the identification of several  
24 necessary transmission improvements, which collectively comprise the first few years  
25 of the multi-year North Shore Loop Plan.<sup>14</sup>

26

---

<sup>12</sup> See *In the Matter of Minn. Power's 2013-2027 Integrated Res. Plan*, Docket No. E015/RP-13-53, ORDER APPROVING RESOURCE PLAN, REQUIRING FILINGS, AND SETTING DATE FOR NEXT RESOURCE PLAN at 7 (Nov. 12, 2013). (Order Point 3).

<sup>13</sup> See *In the Matter of Minn. Power's 2016-2030 Integrated Res. Plan*, Docket No. E015/RP-15-690, ORDER APPROVING RESOURCE PLAN WITH MODIFICATION at 14 (July 18, 2016) (Order Point 3).

<sup>14</sup> See *id.* at Order Point 4.

1 **Q. Are there any new industrial loads proposed for the area?**

2 A. Yes. The Polymet non-ferrous mining operation made progress on its facility in 2016  
3 and Minnesota Power anticipates Polymet will have operations in service three to five  
4 years into the future. The establishment of the Polymet facility would create an  
5 electric demand similar to a small taconite mine near Hoyt Lakes. In mid-2016,  
6 Louisiana Pacific announced its intention to evaluate the Laskin Energy Park as a  
7 potential site for a new siding manufacturing plant to be in service by 2018. While  
8 these additions are not certain, to ensure that the North Shore Loop can support these  
9 additional loads during and after the transition away from baseload generators in the  
10 area, Minnesota Power is also considering the impact of these potential industrial  
11 loads as part of evaluating the North Shore Loop and developing the North Shore  
12 Loop Plan.

13

14 **Q. Is the North Shore Loop Plan only necessary because of these two facilities?**

15 A. No. The need for the North Shore Loop Plan is driven by a complex combination of  
16 the transition away from local coal-fired generators, the need to maintain reliable  
17 electric service to existing residential, commercial, and heavy industrial customers,  
18 the need to provide electric service to new industrial loads, and the age and condition  
19 of the existing transmission assets in the area. Any transmission improvements in the  
20 North Shore Loop Plan that are only necessary because of the development of the  
21 Louisiana Pacific and Polymet industrial facilities will not be constructed unless the  
22 industrial customers move forward with their development plans.

23

24 **Q. Will the cost of those transmission improvements that will only move forward if  
25 the customers complete their developments be charged to those customers?**

26 A. No. Reliability improvements to the transmission system that are networked are  
27 designed to provide benefits to all customers and therefore are recovered through the  
28 MISO Attachment O, of which Minnesota Power retail customers pay their  
29 proportionate share. The most significant of the many inter-related drivers for  
30 transmission upgrades in the North Shore Loop is not new industrial customer  
31 development, but the transition away from baseload coal generators in the area, which



1 has impacts on the local reliability of the local transmission system that must be  
2 mitigated. Minnesota Power will be working closely with Great River Energy and  
3 coordinating through the existing MISO transmission planning process to ensure that  
4 the most cost-effective solutions are identified and implemented to ensure a safe and  
5 reliable transmission system is maintained as the generators in the North Shore Loop  
6 are idled or retired. With regard to new large industrial customer development in the  
7 area, it is important to note that transmission improvements to enable reliable electric  
8 service for these customers would be significantly less if the local North Shore Loop  
9 generation remained online.

10

11 **Q. Please explain what the North Shore Loop Plan entails.**

12 A. The latter parts of the North Shore Loop Plan are still under development while  
13 Minnesota Power continues its evaluation of the reliability impacts of the transition of  
14 the North Shore Loop transmission system and waits on decisions from Louisiana  
15 Pacific and Polymet. Presently, the North Shore Loop Plan consists of several  
16 projects throughout and adjacent to the North Shore Loop transmission system that  
17 are necessary to preserve reliable electric service for the area by mitigating  
18 transmission line and transformer overloads, unacceptably low voltage, and voltage  
19 stability concerns. A variety of different types of transmission improvements have  
20 been recommended for the 2016 and 2017 timeframe, including a large power  
21 transformer addition for load-serving capacity and voltage support, reconfiguration of  
22 an existing substation for increased reliability, capacitor bank additions for voltage  
23 support, asset replacement and modernization due to age and condition and to  
24 eliminate single points of failure, and the development of a new switching station for  
25 increased reliability and voltage support.

26

27 **Q. Does Minnesota Power need a CoN under Minnesota Statutes section 216B.243**  
28 **and/or a Route Permit under Minnesota Statues section 216E?**

29 A. For the planned and potential projects that have been identified through the North  
30 Shore Loop evaluation completed to date, Minnesota Power does not anticipate that  
31 these projects will require a CoN. While there is one new transmission line

1 potentially needed in the 2018 to 2019 timeframe, the new 115 kV line is less than 10  
2 miles in length and does not cross state lines. A CoN, therefore, is not required. It is  
3 likely that the Route Permit for that line will be obtained through the local permitting  
4 authority as allowed under Minn. Stat. § 216E.05.

5  
6 All other potential transmission line upgrades presently identified in the North Shore  
7 Loop Plan would take place on existing rights-of-way at existing or lesser voltage and  
8 therefore not require a CoN or a Route Permit. Since evaluation of the overall North  
9 Shore Loop is still ongoing, additional projects potentially requiring a CoN or Route  
10 Permit from the State of Minnesota may be identified as the overall North Shore Loop  
11 Plan is finalized for the years 2018 to 2020 and beyond.

12  
13 **Q. What North Shore Loop Plan costs have been included in this rate case?**

14 A. Approximately \$20.27 million in nominal dollars is estimated to be spent on the  
15 North Shore Plan between the years 2015-2017.<sup>15</sup> Minnesota Power requests that  
16 these costs be included in base rates. These costs will be incurred to add a second  
17 230 kV/115 kV transformer at an existing substation in the Forbes area, reconfigure  
18 an existing 230 kV substation in the Virginia area, add a capacitor bank in the Babbitt  
19 area, standardize and modernize a legacy 138 kV system by converting it to 115 kV,  
20 add a switching station and several capacitor banks in the Silver Bay area, and  
21 modernize a 115 kV breaker at an existing substation.

22  
23 **Q. Will Great River Energy or its cooperatives served by lines in the North Shore**  
24 **Loop be providing any cost support for the projects included in the North Shore**  
25 **Loop Plan?**

26 A. Minnesota Power does not presently anticipate that Great River Energy will directly  
27 contribute cost support for any of the North Shore Loop Plan projects, because all the  
28 transmission assets involved are owned by Minnesota Power. However, Great River

---

<sup>15</sup> The forecast total amount for the North Shore Plan shown on Exhibit \_\_\_(CEF), Schedule 1 reflects credits received by Minnesota Power during the 2010 to 2013 period for work performed on North Shore Loop assets prior to 2010.

1 Energy compensates Minnesota Power for the use of transmission assets – including  
2 new assets – through the Joint Pricing Zone (“JPZ”), as described elsewhere in my  
3 testimony. Through the JPZ, the cost of Minnesota Power’s North Shore Loop Plan  
4 investments will be shared appropriately by Great River Energy.  
5

6 **Q. What does the Company request the Commission do with the costs for the**  
7 **projects included in the North Shore Loop Plan?**

8 A. Minnesota Power requests that the Commission allow the Company to recover North  
9 Shore Loop Plan project costs totaling \$20.08 million for the costs expended through  
10 2017 in base rates, consistent with the Commission’s July 18, 2016, Order (Order  
11 Point 4) (Docket No. E015/RP-15-690).  
12

13 **3. New Business or Customer Need**

14 a. Nashwauk 230 kV/115 kV Transmission Facility Projects

15 **Q. What are the Nashwauk 230kV/115 kV Transmission Facility Projects**  
16 **(“Nashwauk Transmission Projects”)?**

17 A. The Nashwauk Transmission Projects include four 230 kV transmission lines, two  
18 new substations, and modifications to the existing Blackberry Substation, all in Itasca  
19 County near Nashwauk, Minnesota. Minnesota Power and Nashwauk Public Utilities  
20 obtained a Route Permit from the Commission in Docket No. E280/TL-09-512. The  
21 Nashwauk Transmission Projects were divided into two stages, with the first phase  
22 consisting of construction of approximately 21 miles of new 230 kV transmission  
23 lines (three out of the four proposed lines) connecting the existing Boswell and  
24 Shannon substations to the new Calumet and McCarthy Lake substations. One of the  
25 new 230 kV lines was also designed to support a new Great River Energy 115 kV line  
26 on common structures. The first stage of the Nashwauk Transmission Projects was  
27 placed in service in April 2013. The second stage, if needed, would consist of  
28 construction of a new Blackberry – McCarthy Lake 230 kV line, as well as the  
29 associated modifications at the two substations.  
30

1 **Q. Why were the Nashwauk Transmission Projects needed?**

2 A. The Nashwauk Transmission Projects are networked 230 kV lines that support system  
3 reliability for a large area of northern Minnesota, including Grand Rapids, Nashwauk,  
4 Hibbing, and all the areas between. While a primary purpose of the project was to  
5 supply reliable electric power to our wholesale customer, Nashwauk Public Utilities,  
6 and to the proposed Essar Steel Minnesota LLC (“Essar”) iron mining operation, the  
7 transmission facilities were designed to provide networked transmission connections  
8 to the taconite mine and plant sites while maintaining adequate reliability in the  
9 surrounding transmission system. As such, they also provide benefit for the  
10 surrounding area, including as a critical outlet for power generated at Minnesota  
11 Power’s Boswell Energy Center and in support of reliable delivery to Minnesota  
12 Power and Great River Energy’s customers in the Grand Rapids, Nashwauk, and  
13 Hibbing areas, and all the areas between.

14

15 **Q. Have the Nashwauk Transmission Projects provided improved reliability for**  
16 **other customers?**

17 A. Yes. The first stage of the Nashwauk Transmission Projects, which was placed in  
18 service in April 2013, has continuously supported the reliable operation of the  
19 transmission system since its construction, while also providing a ready source of  
20 electricity to support development of a taconite mine and processing plant at the site.  
21 The second phase of the Nashwauk Transmission Projects was not constructed, and  
22 will not be constructed, unless it becomes needed to support transmission system  
23 reliability in conjunction with potential ultimate load levels (in excess of 300 MW) at  
24 the mine and processing plant site.

25

26 **Q. What was Minnesota Power’s cost estimate for the Nashwauk Transmission**  
27 **Projects at the time it obtained its Route Permit?**

28 A. Minnesota Power estimated the first phase of the Nashwauk Transmission Projects  
29 would cost \$27.78 million in 2009 dollars, excluding transformers and low-side  
30 equipment not owned by Minnesota Power.

31

1 **Q. What did it cost Minnesota Power to construct the Nashwauk Transmission**  
 2 **Projects?**

3 A. Minnesota Power spent \$31.14 million, in nominal dollars, to construct the first phase  
 4 of the Nashwauk Transmission Projects between the years 2011 and 2013. The  
 5 Company received and applied sales tax credits through 2015 actuals and 2016  
 6 forecast total project costs. Using the Handy-Whitman Indices to account for  
 7 inflation, the costs associated with the first stage of the Nashwauk Transmission  
 8 Projects are equivalent to \$30.01 million in 2009 dollars, approximately \$2.23 million  
 9 above the original estimate of \$27.78 million in 2009 dollars and \$3.36 million  
 10 dollars above the nominal costs. The cost estimate and actual nominal cost for the  
 11 Nashwauk Transmission Projects to date are summarized in Table 8. The actual total  
 12 project cost accounts for the funding received by the Nashwauk Public Utilities  
 13 Commission provided toward the first phase of the project.

14  
**Table 8**  
**Nashwauk 230 kV / 115 kV Transmission Facility Projects<sup>+</sup>**  
**(Dollars in Millions)**

<b>Project Description</b>	<b>CoN Project Estimate</b>	<b>Route Permit Project Estimate</b>	<b>Actual Total Project Cost</b>	<b>Actual Total Project Costs (Adjusted)<sup>#</sup></b>
Nashwauk Project	N/A	\$27.78	\$31.14	\$30.01
Dates (Relevant)	N/A	2009	2010-2016	2009
<small># Handy-Whitman is used to determine the de-escalated costs back to dates of project estimates.</small>				
<small>+ MPUC Docket No. E280/TL-09-512</small>				

15  
 16 **Q. Why were final costs of the Nashwauk Transmission Projects higher than**  
 17 **estimates provided in the route permit proceeding?**

18 A. The primary reasons for the cost increase can be attributed to the fact that the  
 19 Company did not include project indirect costs (AFUDC, overheads, and allocations,  
 20 etc.) in the original route permit estimates. In addition, easement acquisition  
 21 difficulties, including navigating previously-not-applicable Lessard Sams Outdoor  
 22 Heritage Council operating procedures and the 94 Line removal, the volume of  
 23 matting required to construct in challenging conditions (approximately 22,000 mats  
 24 and additional restoration), and the need for optical ground wire that had not been

1 included in the initial estimate. Additionally, the overall project schedule resulted in  
2 a substantial amount of overheads that were not included in the initial estimate.  
3 These quantified costs to account for the \$3.36 million dollars are summarized in  
4 Table 9.

5  
6 **Table 9**  
7 **Nashwauk Transmission Project Cost Summary**

<b>Cost Driver</b>	<b>Estimated Cost Impact</b>
Easement acquisition and permitting	\$224,000
Optical Ground Wire	\$335,500
Matting, vegetation clearing, and restoration	\$700,000
Minnesota Power indirect & overheads (AFUDC)	\$2,100,000

8  
9 **Q. Why were five miles of the Nashwauk Transmission Projects constructed as 230**  
10 **kV/115 kV double-circuit?**

11 A. When the Nashwauk Transmission Projects were originally permitted, all 230 kV line  
12 segments were permitted as single circuit facilities. As the project was being  
13 engineered, Great River Energy expressed a need to build a 115 kV line to a  
14 cooperative distribution substation located near one of the proposed 230 kV  
15 transmission line routes. To accommodate the Great River Energy need, a minor  
16 alteration was filed to allow for a section of 230 kV line to be double circuited with  
17 the Great River Energy 115 kV Line. Continued transmission system planning and  
18 construction collaboration with area transmission owners benefits all customers  
19 served in northern Minnesota.

20  
21 **Q. Did Great River Energy provide funding to Minnesota Power for this**  
22 **modification?**

23 A. Yes. Great River Energy paid Minnesota Power approximately \$3.5 million for this  
24 additional work. This Great River Energy credit was included as a contribution in aid  
25 of construction to reduce the total project cost and is reflected in the final project  
26 costs noted in Table 8.

1 **Q. What steps did Minnesota Power take to limit risk and control costs associated**  
2 **with construction of the Nashwauk Transmission Projects?**

3 A. The Nashwauk Transmission Projects construction risk exposure was managed by the  
4 Company requiring that Essar provide acceptable security guarantees (e.g., letter of  
5 credit, acceptable corporate parent guarantee, etc.) to Minnesota Power as we  
6 achieved key project milestones or construction “gates.” Essar was required to meet  
7 the security agreement terms prior to the Company proceeding with project  
8 construction. This allowed the Company to stop progress at logical points if the  
9 customer did not meet their contractual obligations. Minnesota Power has been able  
10 to use security guarantee funds to cover revenue requirements and electrical service  
11 obligations related to the project.

12  
13 As another measure of risk mitigation, Minnesota Power was very deliberate in  
14 designing elements and selecting equipment and materials for the substations and  
15 transmission lines that were capable of being absorbed and readily “repurposed” back  
16 into the Company’s system for other projects or maintenance if Essar were to breach  
17 the terms of the agreement prior to the facilities being placed into service. Though  
18 this was not the ideal approach to executing a project, it was the most prudent  
19 approach to minimize risk to the Company and our customers while still complying  
20 with the Company’s obligation to provide open transmission access for  
21 interconnecting customers such as the Nashwauk Public Utilities Commission.

22  
23 **Q. Did Minnesota Power prudently incur the costs it spent to complete the**  
24 **Nashwauk Transmission Projects?**

25 A. Yes. The costs incurred by the Company to complete the Nashwauk Transmission  
26 Projects were prudently and reasonably incurred to complete this necessary project.  
27 In the event the additional phases are required, Minnesota Power will track and report  
28 to the Commission on the costs it incurs while completing construction. The first  
29 phase facilities are in service and provide wholesale transmission service to the City  
30 of Nashwauk, and provide improved reliability for the broader region.

31

1 **Q. Why should the Minnesota Power retail customers pay for the in-service**  
2 **Nashwauk Transmission Projects?**

3 A. The Nashwauk Transmission Projects were designed to provide safe, reliable, and  
4 cost-effective transmission service to a new customer with a significant electric load.  
5 Although the project was prompted by the Nashwauk Public Utilities Commission's  
6 service to a single customer, the size of the load and the phased nature of the potential  
7 growth, required the Company to design the service at transmission voltages. This  
8 transmission solution also provided the opportunity for the Company to improve the  
9 overall reliability for all customers across the area.

10  
11 The presence of wholesale customers on the Minnesota Power Transmission System  
12 provides benefits for our retail customers. Wholesale customers must pay  
13 transmission costs under MISO Attachment O, thereby reducing transmission costs  
14 for our retail customers.

15  
16 **Q. What does the Company request the Commission do with the costs for the**  
17 **Nashwauk Transmission Projects?**

18 A. Minnesota Power requests that the Commission allow the Company to recover the  
19 Nashwauk Transmission Projects cost in base rates.

20  
21 b. 39 Line 115 kV Transmission Facility Project

22 **Q. What is the 39 Line 115 kV Transmission Facility Project (“39 Line Project”)?**

23 A. The 39 Line Project is a 2.9-mile, 115 kV transmission line in St. Louis County near  
24 Eveleth, Minnesota, that obtained a Route Permit from the Commission in Docket  
25 No. E015/TL-12-1123.

26  
27 **Q. Was a CoN obtained for the 39 Line Project?**

28 A. No. Because the 39 Line Project did not meet any of the requirements for the CoN  
29 outlined in Minn. Stat. § 216B.243, a CoN was not obtained for the 39 Line Project.

30



1 **Q. Why was the 39 Line Project needed?**

2 A. The 39 Line Project was needed to allow for the removal of an existing segment of  
3 115 kV line located on mining property by re-establishing the 115 kV connection  
4 between the Virginia area and the Hoyt Lakes area that would have been lost by  
5 removal of the existing line. The existing line was located in an area to be mined by  
6 United Taconite. The 39 Line Project allowed 1.9 miles of existing 115 kV  
7 transmission line to be relocated without compromising the reliability of the  
8 surrounding transmission system for customers in the Virginia, Eveleth, and Hoyt  
9 Lakes areas.

10

11 **Q. Why should Minnesota Power customers pay for this project?**

12 A. The 39 Line Project preserved the quality and reliable operation of the transmission  
13 system in the area. Although the relocation was prompted by United Taconite,  
14 exercising their easement rights to require the Company to relocate our transmission  
15 facilities, the project was necessary and benefits customers in the entire East Range  
16 area, including Virginia, Eveleth, Hoyt Lakes, and all areas between.

17

18 **Q. What were the land rights Minnesota Power held for the 39 Line right-of-way  
19 that needed to be relocated?**

20 A. When the segment of 39 Line designated for removal was constructed in 1990,  
21 Minnesota Power was only able to obtain a license with removal requirements from  
22 Eveleth Taconite (United Taconite's predecessor) instead of a customary permanent  
23 easement that Minnesota Power obtains for the vast majority of its transmission  
24 facilities. That license allowed Minnesota Power's transmission line to be routed on  
25 United Taconite's land but required that, in the event the license agreement expired or  
26 was terminated or a notice of relocation was provided by United Taconite, Minnesota  
27 Power would relocate the transmission line within two years. United Taconite  
28 notified Minnesota Power in December 2011 by issuing a Notice to Relocate and  
29 Elevate Electric Transmission Line, as required by the license agreement.

30

1           Although easements are preferred for transmission facilities, given the varying  
2           mining lands in northern Minnesota, the varying rates at which mining has progressed  
3           in the area, and the encumbrance placed on potential mining lands by the construction  
4           of transmission lines, licenses have been and continue to be a reasonable approach to  
5           transmission land rights on mining lands.

6

7           **Q.    Are you aware of other public or private infrastructure that has been required**  
8           **to move or relocate due to easements associated with mining?**

9           A.    Yes.  The Minnesota Department of Transportation (“MnDOT”) had similar land  
10          right and relocation terms with a predecessor of Cliffs Natural Resources Inc. when  
11          they built U.S. Highway 53 between Eveleth and Virginia, Minnesota in 1960.  The  
12          final relocation project Environmental Impact Statement (“EIS”) issued in September  
13          of 2015 cited the justification for the relocation as the legal right the mining company  
14          had to terminate the easement and request that MnDOT relocate the highway to  
15          facilitate the mining operation.  The total capital construction costs for the project  
16          were estimated to cost between \$180 and \$240 million dollars.

17

18          **Q.    Why is the MnDOT experience relevant to Minnesota Power’s experience with**  
19          **the 39 Line?**

20          A.    The MnDOT experience demonstrates that even the State of Minnesota was unable to  
21          obtain more permanent land rights for a major highway through mineral lands in this  
22          area.  Both the State of Minnesota and Minnesota Power had to relocate infrastructure  
23          to ensure that the mineral interests of the state could be mined.

24

25          **Q.    Did Minnesota Power consider any alternatives to relocation that could have**  
26          **accommodated United Taconites mining plans?**

27          A.    Yes.  Minnesota Power first evaluated the possibility of not replacing the segment,  
28          but determined that the reliability of the system serving customers in and around area  
29          communities, including Hoyt Lakes, Eveleth, and Virginia, Minnesota would be  
30          degraded.  Minnesota Power concluded that reconfiguring the segment and re-

1 establishing the transmission connection was the necessary solution for maintaining  
2 appropriate system reliability.

3

4 **Q. When was the 39 Line Project energized?**

5 A. The 39 Line Project was placed in service on May 1, 2014.

6

7 **Q. What was Minnesota Power’s cost estimate for the 39 Line Project at the time it  
8 obtained its Route Permit?**

9 A. Minnesota Power estimated the 39 Line Project would cost \$2 million, in 2012  
10 dollars.

11

12 **Q. What was the final cost of the 39 Line Project?**

13 A. Minnesota Power spent \$5.77 million, in nominal dollars, to construct the 39 Line  
14 Project between the years 2012 and 2015. Using the Handy-Whitman Indices to  
15 account for inflation, the 39 Line Project costs are equivalent to \$5.60 million in 2012  
16 dollars, approximately \$3.60 million above the original estimate of \$2.0 million in  
17 2012 dollars. The cost estimate and the actual total cost for the 39 Line Project are  
18 summarized in Table 10.

19

**Table 10**  
**39 Line 115 kV Transmission Facility Project<sup>+</sup>**  
**(Dollars in Millions)**

<b>Project Description</b>	<b>CoN Project Estimate</b>	<b>Route Permit Project Estimate</b>	<b>Actual Total Project Cost</b>	<b>Actual Total Project Costs (Adjusted)<sup>#</sup></b>
39 Line Project	N/A	\$2.00	\$5.77	\$5.60
Dates (Relevant)	N/A	2012	2012-2015	2012
<b># Handy-Whitman is used to determine the de-escalated costs back to dates of project estimates.</b>				
<b>+ MPUC Docket No. E015/TL-12-1123<sup>16</sup></b>				

20

---

<sup>16</sup> Actual Total Project Cost includes the amount forecasted to be spent in 2016.

1 **Q. Why were final costs of the 39 Line Project higher than estimates provided in the**  
2 **Route Permit proceeding?**

3 A. The primary drivers for the cost increase are construction difficulties associated with  
4 geographical features, unanticipated subterranean conditions, and a construction  
5 schedule that had to be accelerated in light of a route permit process that took longer  
6 than the six months anticipated under Minn. Stat. § 216E.03, subd. 7 for the  
7 alternative permitting process.<sup>17</sup>

8

9 **Q. What challenges were encountered during construction?**

10 A. First, the estimate included in the Route Permit application did not account for the  
11 more densely spaced structures necessary to follow the curves of the road followed by  
12 the permitted route. Additionally, the estimate did not include additional funds  
13 necessary to complete vegetation removal. The project also required a  
14 reconfiguration of the transmission system in the area, merging two 115 kV  
15 transmission line facilities into one “three-terminal” facility, that required  
16 modifications of the relaying and communications systems at the substation  
17 endpoints. This equipment and labor was not included in the initial estimate. As  
18 construction was starting, Minnesota Power was informed of an existing wetland  
19 bank that United Taconite had designated with the state, which was crossed by the  
20 permitted route. This wetland bank required additional permitting and engineering  
21 constraints not previously identified. Additionally, the U.S. Army Corps of  
22 Engineers increased Minnesota Power’s wetland mitigation ratio from what was  
23 originally used, requiring additional wetland mitigation.

24

25 During construction, an undocumented municipal waterline was discovered in the  
26 transmission line route. Because accurate records were not available to identify the  
27 location of this waterline prior to construction, it was damaged during construction.

28 In addition to repairing the damaged pipeline, Minnesota Power did a significant

---

<sup>17</sup> The Route Permit Application was filed on October 10, 2012. The Commission’s Route Permit was issued on January 13, 2014. The Company’s first plan and profile compliance filing was filed on January 15, 2014, demonstrating the urgency of the project’s construction progress.

1 amount of over-excavation in the pole locations adjacent to the previously-  
 2 unidentified waterline in order to accurately locate it. An electrical induction study  
 3 was also necessary to identify mitigation for the electrical impacts on the pipeline due  
 4 to the proximity of the new transmission line. All of these challenges were in  
 5 addition to accommodating the timing needs of United Taconite, which was in the  
 6 predicament of both being served directly by the 39 Line (limiting outage availability  
 7 due to power needs of the mining facility) and needing it to be removed as soon as  
 8 possible to avoid negative impacts to mining operations. Cost increases experienced  
 9 above the estimate in the Route Permit application are summarized in Table 11.

10  
 11 **Table 11**  
 12 **39 Line Project Costs Above Estimate**

<b>Cost Driver</b>	<b>Estimated Cost Impact<sup>18</sup></b>
Inadequate estimate, including omitted AFUDC and overheads	\$1,700,000
Vegetation clearing and matting	\$652,000
Relay equipment at three substations	\$120,000
Unanticipated 16 Line work for 39 Line crossing	\$300,000
Construction contractor increase from construction estimate	\$841,000

13  
 14 **Q. Are any costs associated with the 39 Line Project included in the TCR?**

15 A. No. Minnesota Power requested that this project be included in the TCR in Docket  
 16 No. E015/15-472; however, the Commission denied recovery in the rider because the  
 17 project did not obtain a CoN and also did not meet one of the CoN exemptions  
 18 specified in Minn. Stat. § 216B.243, subd. 8.

19  
 20 **Q. Did Minnesota Power prudently incur the costs it spent to complete the 39 Line**  
 21 **Project?**

22 A. Yes. The costs incurred by the Company to complete the 39 Line Project were  
 23 prudently and reasonably incurred to complete this necessary project.

---

<sup>18</sup> These costs also do not include sales tax credits that were received by the Company after the work was completed for this project.

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31

**Q. What does the Company request the Commission do with the costs for the 39 Line Project?**

A. Minnesota Power requests that the Commission allow the Company to recover the 39 Line Project costs in base rates.

c. Canisteo 115kV Transmission Facility Project

**Q. What is the Canisteo 115 kV Transmission Facility Project (“Canisteo Project”)?**

A. The Canisteo Project includes the construction of two new 5-mile, 115 kV lines extending from an existing Minnesota Power 115 kV Line (“28 Line”) to a new Canisteo 115/14 kV Substation in Itasca County, Minnesota near the cities of Coleraine and Bovey.

**Q. Was a CoN obtained for the Canisteo Project?**

A. No, because the Canisteo Project did not meet any of the requirements for the CoN outlined in Minn. Stat. § 216B.243, a CoN was not obtained for the Canisteo Project. However, Minnesota Power obtained a Route Permit for the Canisteo Project from the Commission in Docket No. E015/TL-13-805.

**Q. Why was the Canisteo Project needed?**

A. The Canisteo Project was needed to supply reliable electric power to a new Magnetation iron ore concentrate plant and maintain adequate reliability of the surrounding transmission system. Specifically, the Canisteo Project was designed to provide networked transmission connections to the new Canisteo Substation (the primary source of power for the Magnetation plant) while reducing outage exposure for all customers served from the 30-mile 28 Line.

**Q. What was Minnesota Power’s cost estimate for the Canisteo Project at the time it obtained its Route Permit?**

A. Minnesota Power estimated the Canisteo Project would cost \$6.2 million, in 2013 dollars.

1  
2  
3  
4  
5  
6  
7  
8  
9

**Q. What was the final cost of the Canisteo Project?**

A. Minnesota Power spent \$13.12 million, in nominal dollars, to construct the Canisteo Project between the years 2013 and 2015. Using the Handy-Whitman Indices to account for inflation, the Canisteo Project costs are equivalent to \$12.90 million in 2013 dollars, approximately \$6.7 million above the original estimate of \$6.2 million in 2013 dollars. The Canisteo Project cost estimate and actual total project cost are summarized in Table 12.

**Table 12**  
**Canisteo 115kV Transmission Facility Project<sup>+</sup>**  
**(Dollars in Millions)**

<b>Project Description</b>	<b>CoN Project Estimate</b>	<b>Route Permit Project Estimate</b>	<b>Actual Total Project Cost</b>	<b>Actual Total Project Costs (Adjusted)<sup>#</sup></b>
Canisteo Project	N/A	\$6.20	\$13.12	\$12.90
Dates (Relevant)	N/A	2013	2013-2015	2013
<sup>#</sup> Handy-Whitman is used to determine the de-escalated costs back to dates of project estimates.				
<sup>+</sup> MPUC Docket No. E015/TL-13-805				

10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23

**Q. Why were final costs of the Canisteo Project higher than estimates provided in the Route Permit proceeding?**

A. The cost increases for the Canisteo Project were driven primarily by the fact that the Route Permit estimate was not revised to reflect the scope of the final route permit, which included construction of two 115 kV lines verses a single line. This oversight accounted for \$2.3 million dollars of additional expense when compared to the original Route Permit estimate. Costs also increased due to (1) the need for extensive vegetation clearing and use of matting (both purchased and placed), and right-of-way restoration after matting removal, and (2) the construction contractors' increase over the original preliminary construction estimate. The construction contractors' cost increase and the extensive use of matting were driven by the challenges of construction in northern Minnesota wetland conditions. The changes were in turn driven by a project schedule that required construction to commence in late summer

1 and early fall, resulting in the extensive use of timber mats to minimize impacts to  
2 wetlands. The Company did not fully anticipate the full scope and magnitude of the  
3 construction mitigation necessary at the time it prepared the estimate.  
4

5 **Q. Can you provide a breakdown of the cost increases for the Canisteo Project?**

6 A. Yes. The quantifiable cost increases associated with the Canisteo Project  
7 construction are summarized in Table 13.  
8

9 **Table 13**  
10 **Canisteo Project Cost Summary**

<b>Cost Driver</b>	<b>Estimated Cost Impact</b>
Clearing and matting placement expenses	\$2,650,000
Matting (materials) used matting from NERC Reliability Projects	\$360,000
Line materials	\$590,000
Minnesota Power indirect expenses and overheads	\$800,000
Construction contractors preliminary estimate increase <sup>19</sup>	\$2,300,000

11  
12 **Q. Are any costs associated with the Canisteo Project included in the TCR?**

13 A. No, because the Company has not made a request to include the project in the TCR.  
14

15 **Q. Why should Minnesota Power retail customers pay for this project?**

16 A. The project was designed to provide safe, reliable, and cost-effective transmission  
17 service to a new customer with a significant electric load. Although the project was  
18 prompted by a single customer, the size of the load required the Company to provide  
19 service at transmission voltages. This transmission solution also provided the  
20 opportunity for the Company to improve the overall reliability benefits for all  
21 customers across the area.  
22

---

<sup>19</sup> The permit estimate did not reflect the final scope of the project.



1 **Q. Did Minnesota Power prudently incur the costs it spent to complete the Canisteo**  
2 **Project?**

3 A. Yes. The costs incurred by the Company to complete the Canisteo Project were  
4 prudently and reasonably incurred to complete this necessary project.  
5

6 **Q. What does the Company request the Commission do with the costs for the**  
7 **Canisteo Project?**

8 A. Minnesota Power requests that the Commission allow the Company to recover the  
9 Canisteo Project costs in base rates.  
10

11 **4. Regional Expansion Projects**

12 a. Bemidji – Grand Rapids 230 kV Transmission Project

13 **Q. What is the Bemidji Project?**

14 A. The single-circuit, 230 kV Project is approximately 70 miles in length and connects  
15 the Wilton Substation, near Bemidji, Minnesota, and the Boswell Substation, in  
16 Grand Rapids, Minnesota. The Bemidji Project was approved by the Commission in  
17 Docket Nos. E017,E015,ET6/CN-07-1222 and E017,E015,ET6/TL-07-1327. It was  
18 energized and placed in service in 2012 to improve reliability for the Red River  
19 Valley, Bemidji, Grand Rapids, and north central Minnesota.  
20

21 **Q. Was a provisional cost cap set for the Bemidji Project?**

22 A. In its Order in Docket No. E017/M-13-103, the Commission found the cost cap for  
23 current TCR recovery related to the Bemidji Project to be \$74 million. This equates  
24 to a cost cap of \$6.882 million for Minnesota Power's ownership interest of 9.3  
25 percent in the Bemidji Project.  
26

27 **Q. What was Minnesota Power's final cost for the Bemidji Project?**

28 A. Minnesota Power's final cost for the Bemidji Project was \$10.88 million. The cost  
29 estimate and the actual cost for the Bemidji Project are summarized in Table 14.

1

**Table 14**  
**Bemidji-Grand Rapids 230 kV Transmission Facility Project<sup>+</sup>**  
**(Dollars in Millions)**

<b>Project Description</b>	<b>CoN Project Estimate<sup>^</sup></b>	<b>Route Permit Project Estimate</b>	<b>Actual Total Project Cost (Nominal)<sup>^</sup></b>
Bemidji – Grand Rapids	\$6.88	N/A	\$10.88
Dates (Relevant)	N/A <sup>20</sup>	2013	2012
+ MPUC Docket No. E017,E015,ET6/CN-07-1222 and E017,E015,ET6/TL-07-1327			
<sup>^</sup> MN Power Portion of the Project			

2

3 **Q. What costs have been included in Minnesota Power’s TCR for the Bemidji**  
4 **Project?**

5 A. In our TCR, Minnesota Power has only sought recovery of revenue requirements  
6 related to the first \$6.882 million.

7

8 **Q. Is Minnesota Power seeking recovery of the additional \$3.99 million in the rate**  
9 **case?**

10 A. Yes. Minnesota Power is requesting that the Commission approve, and the test year  
11 include, the additional project costs above the CoN estimate for the Bemidji Project  
12 as these costs were prudently and reasonably incurred.

13

14 **Q. Are you aware of other CapX2020 partners that have successfully recovered**  
15 **expenses that totaled above the CoN estimate for the Bemidji Project?**

16 A. Yes. It is my understanding that Xcel Energy has been recovering those amounts that  
17 were identified as above their respective CoN estimates since its 2012 rate case  
18 (Docket No. E002/GR-12-961). Minnesota Power is requesting similar treatment for  
19 its investment in this project.

20

---

<sup>20</sup> The cost cap for the Bemidji Project was set by the Commission in nominal dollars. This limited Minnesota Power to recovering up to the first \$6.882 million it invested in the Bemidji Project, over the life of the project, through the TCR.

1 **Q. Why did the costs for the Bemidji Project increase from those estimates**  
2 **approved by the Commission?**

3 A. Xcel Energy included an extensive reconciliation of the Bemidji Project costs to the  
4 estimates included in the Bemidji Project CoN in its August 31, 2012, Reply  
5 Comments in Docket No. E002/M-12-50. A copy of the relevant portions of those  
6 Reply Comments are included as Exhibit \_\_\_\_ (CEF), Schedule 3. While that  
7 reconciliation was prepared when the project was approximately 98 percent complete,  
8 the main drivers were unchanged upon completion. Those drivers were:

- 9 • Winter Construction: The Bemidji Project incurred \$15.4 million (Total Project)  
10 to purchase, install, and remove additional wetland protection mats due to warm  
11 winter temperatures during 2011 to 2012, which was \$9.6 million (Total Project)  
12 more than originally estimated. During normal winters, wetlands in the area  
13 freeze so that construction with typical protective measures can continue. The  
14 2011 to 2012 winter was one of the warmest on record and the wetlands in the  
15 project area did not freeze sufficiently to support construction equipment.  
16 Continuing construction was more cost effective than waiting until spring but  
17 required additional equipment to protect the wetland areas against damage from  
18 heavy traffic and use of construction equipment. To protect the landscape, the  
19 Bemidji Project purchased, installed, and removed an additional 20,000 mats.
- 20 • Permitting, Right-of-Way, and Legal: Permitting, right-of-way, and legal  
21 expenses were always anticipated as part of the Bemidji Project, but they were not  
22 expressly quantified in the CoN. Total Bemidji Project permitting, right-of-way,  
23 and legal costs were \$26.90 million (Total Project).
- 24 • Associated Facilities: Several additional associated facilities were identified as  
25 being needed for the project to be reliably interconnected to substations and the  
26 underlying transmission system. This added an additional \$2.6 million (Total  
27 Project) to the project.
- 28 • Other Route-Related Costs: Portions of the Bemidji Project parallel the Great  
29 Lakes Gas Transmission pipeline along U.S. Highway 2, which required the  
30 installation of special equipment to mitigate the induction of electrical currents  
31 across pipeline facilities. Without the equipment, the effectiveness of the

1 pipeline's corrosion system would be reduced. The Bemidji Project incurred  
2 approximately \$1.9 million (Total Project) for this pipeline induction mitigation.  
3 Tree clearing and road restoration costs also increased approximately \$1.0 million  
4 (Total Project) based on the final route running through areas where the trees  
5 were larger and more dense than anticipated.  
6

7 **Q. Did Minnesota Power prudently incur the costs it spent to complete the Bemidji**  
8 **Project?**

9 A. Yes. The costs incurred by the Company to complete the Bemidji Project were  
10 prudently and reasonably incurred to complete this necessary project.  
11

12 **Q. What does the Company request the Commission do with the costs for the**  
13 **Bemidji Project?**

14 A. Minnesota Power requests that the Commission allow the Company to recover the  
15 Bemidji Project costs in base rates.  
16

17 b. Monticello – Fargo 345 kV Transmission Facility Project

18 **Q. What is the Fargo Project?**

19 A. The Fargo Project consists of a 238-mile, 345 kV transmission line (built on double-  
20 circuit-capable structures) from Monticello, Minnesota, to a new Bison Substation  
21 west of Fargo, North Dakota. Minnesota Power holds a 14.7 percent ownership  
22 interest in the Fargo Project. The Fargo Project is one of the CapX2020 projects.  
23

24 **Q. What was the estimated cost of the Fargo Project when approved by the**  
25 **Commission?**

26 A. In 2009, the May 22, 2009, Commission Order approved the Fargo Project at a cost  
27 between \$500 million and \$640 million (Docket No. ET2,E002,*et al.*/CN-06-1115).  
28 That Order also identified the potential for lower-voltage upgrades estimated to cost  
29 between \$75 million and \$100 million. Both estimates were in 2007 dollars.  
30

1 **Q. What costs have been included in Minnesota Power’s TCR?**

2 A. Minnesota Power has included the amounts it incurred through the end of 2014 in its  
3 TCR (Docket No. E015/M-15-472).

4  
5 **Q. Were more costs incurred by Minnesota Power after the end of 2014?**

6 A. Yes. The Fargo Project was not fully energized until April 2, 2015. There were  
7 additional costs incurred between the end of 2014 and 2015 to complete the Fargo  
8 Project. The Fargo Project cost estimate and actual cost are summarized in Table 15.  
9

**Table 15<sup>21</sup>**  
**Fargo 345 kV Transmission Facility Project<sup>+</sup>**  
**(Dollars in Millions)**

<b>Project Description</b>	<b>CoN Project Estimate</b>	<b>Route Permit Project Estimate</b>	<b>Actual Total Project Cost (Nominal)</b>	<b>Actual Total Project Costs (Adjusted)<sup>#</sup></b>
Fargo Project – 345 kV	\$94.8 <sup>22</sup>	N/A	\$100.12	\$87.26
Dates (Relevant)	2007	2013	2010-2016	2007
<b># Handy-Whitman is used to determine the de-escalated costs back to dates of project estimates.</b>				
<b>+ MPUC Docket No. ET2,E002,et al./CN-06-1115</b>				

10

11 **Q. Why is the final cost for the Fargo Project less than the estimate?**

12 A. The Fargo Project was completely energized in April 2015 and completed under the  
13 CoN estimate. The Fargo Project was constructed in phases, which provided the  
14 opportunity to develop project-specific lessons learned and efficiencies that could  
15 then be applied to the later phases. Additionally, significant costs were saved as a  
16 result of the opportunity to self-perform many of the civil construction activities in  
17 the later phases of the Fargo Project.  
18

<sup>21</sup> Actual Total Project Cost includes the amount forecasted to be spent in 2016.

<sup>22</sup> As shown in Table 2 of the Department’s September 29, 2010, Comments in Docket No. E015/M-10-799, the estimated project costs for the Fargo Project for Minnesota Power ranged from approximately \$94 million to \$110 million.

1 **Q. Did Minnesota Power prudently incur the costs it spent to complete the Fargo**  
2 **Project?**

3 A. Yes. The costs incurred by the Company to complete the Fargo Project were  
4 prudently and reasonably incurred to complete this necessary project.

5

6 **Q. What does the Company request the Commission do with the costs for the Fargo**  
7 **Project?**

8 A. Minnesota Power requests that the Commission allow the Company to recover the  
9 Fargo Project costs in base rates.

10

11 **Q. What is the Company’s overall request with respect to the transmission capital**  
12 **included in this proceeding?**

13 A. Minnesota Power requests that the Commission find that costs incurred for  
14 transmission capital investments were reasonable and prudent. While some project  
15 cost estimates were lower than final costs, some project cost estimates were higher  
16 than final costs. These transmission projects were all necessary and costs were  
17 prudently incurred.

18

19 **B. Distribution Capital Investments**

20 **Q. How do you determine your distribution function capital investment plan?**

21 A. We determine our capital investment plan to ensure we meet customer, community,  
22 and system needs. Larger projects, generally greater than \$50,000, are budgeted  
23 individually and considered specific “discrete projects.” Smaller projects, and those  
24 taking place year after year, are considered “routine projects.” While the sub-projects  
25 that comprise the routine projects are given individual work order numbers, their  
26 aggregate costs are combined for budgeting purposes.

27

28 Specific capital projects are identified through a rigorous planning process that results  
29 in short- and long-term investment plans including those targeted to address customer  
30 needs and maintain system reliability. The distribution function has a well-defined  
31 process for identifying, ranking, and budgeting electric line and distribution

1 substation projects. A key step in the process is the identification of potential  
2 problems or risks on the system, including those that threaten reliability and  
3 regulatory compliance. We identify these potential problems or risks to the system by  
4 reviewing system performance to ensure we consider reliability and load data to  
5 assess feeder and substation performance. We then conduct contingency analyses to  
6 identify the reliability impacts for certain system component failure to identify the  
7 highest risk areas.

8

9 In the capital budgeting process, potential solutions or mitigations of these risks are  
10 identified as projects and are screened and evaluated against each other based on their  
11 costs, how effectively they address certain risks, and the severity of the risk. After  
12 the ranking is completed, business leadership reviews the list, the level of risk  
13 associated with the various projects, as well as available capital funding to determine  
14 which projects will be implemented.

15

16 **Q. What is the process for budgeting the routine projects you described above?**

17 A. The distribution function evaluates the historic capital investments in routine projects  
18 as the initial step in developing the next year's routine projects. We also look to  
19 economic trends, projected customer additions, current and forecasted labor costs,  
20 and any changes to trends in material costs. In addition, the Company completes an  
21 annual evaluation of the actual completed construction costs for distribution service  
22 extension and uses this information in the budgeting process.

23

24 Other routine blanket projects are identified and budgeted to meet projected needs for  
25 line relocations due to road realignments, smaller capacity projects, street lighting,  
26 reliability programs, fleet purchases, and tools. Funding levels for these routine  
27 projects are based primarily on recent historical expenditure trends, with additional  
28 insight as available from local or community resources.

29

1 **Q. Please describe the components for the Minnesota Power distribution function**  
2 **capital investment.**

3 A. Table 16 provides a summary of the distribution function capital investment plan. As  
4 shown, the distribution capital investment plan is comprised of distribution base,  
5 substation/capacity, and fleet and equipment.  
6

**Table 16**  
**Distribution Capital Invested**  
**2010-2017 (Dollars in Millions)**

Actual & Budget invested in the respective year							
2010 Actual	2011 Actual	2012 Actual	2013 Actual	2014 Actual	2015 Actual	2016 Forecast	2017 Budget
\$22.54	\$21.90	\$23.40	\$28.30	\$21.40	\$25.00	\$29.10	\$33.30

7

8 **Q. How do the distribution function capital investment projects undertaken in 2010**  
9 **and 2011 compare to those undertaken in 2012 and 2013?**

10 A. In 2012, Minnesota Power increased its distribution capital spending to begin the  
11 replacement of a paper insulated lead cable (“PILC”) underground distribution cable  
12 network system (“PILC System”) which serves downtown Duluth and the Canal Park  
13 district of Duluth. The existing PILCs are approximately 80 to 90 years old and have  
14 recently demonstrated a significantly higher frequency of faulting, resulting in  
15 unplanned customer outages. The Company has increased its replacement activities  
16 of this aged infrastructure since 2012 and will continue beyond the 2017 test year.  
17 The distribution function capital investment committed to this project is in the range  
18 of \$1.00 million to \$2.00 million per year, from 2012 forward. Additionally, the  
19 advanced metering infrastructure and technologies (“AMI”) meter replacement  
20 program, while initiated in 2010, increased capital investment in 2012 through 2014,  
21 with a significant investment amount made in 2013 to increase meter deployments  
22 and the supporting communications infrastructure.  
23

24 **Q. How do the 2016 forecast and 2017 budget compare to Minnesota Power’s**  
25 **historic distribution capital investments?**

26 A. Minnesota Power’s distribution function capital investments for 2016 are higher than  
27 historic investments because of three new or refurbished 115 kV-to-distribution-



1 voltage substations (Hat Trick, 15th Avenue West, and Canosia). It is not typical to  
2 have that many new 115 kV-to-distribution-voltage substations in one year for  
3 Minnesota Power. The 2017 budget, while other distribution capital investments  
4 return to levels more similar to historic investments, includes an increased amount for  
5 the purchase of fleet vehicles and equipment for the Meter Data Management  
6 (“MDM”) project. The cost of fleet vehicles was previously accounted for entirely in  
7 O&M as the fleet vehicles were leased. As discussed later in my testimony,  
8 Minnesota Power is undertaking a transition to fleet vehicle ownership as a cost  
9 containment measure.

10

11 **Q. Are there other distribution capital investment initiatives that Minnesota Power**  
12 **is seeking to include in base rates?**

13 A. Yes. Minnesota Power has invested \$13.2 million dollars in AMI since its last rate  
14 review. Minnesota Power has included \$3.5 million dollars in the 2017 test year for  
15 meter and AMI purchases. This is one dimension of the key investments in  
16 technology and data infrastructure necessary to establish the distribution platform  
17 needed to enhance the customer experience and enable the smart grid modernization.  
18 Minnesota Power also invested \$17.38 million in a new CC&B system that went into  
19 service in 2015.

20

21 The other future capital investments will include costs associated with the MDM  
22 which will be an extension of our CC&B system.

23

24 **1. Distribution Infrastructure**

25 **Q. Please provide some examples of other distribution capital investments the**  
26 **Company is currently undertaking.**

27 A. Minnesota Power is currently undertaking two modernization projects that are  
28 necessary to ensure the reliability of the Distribution System. One is the replacement  
29 of PILCs that provide distribution service in downtown Duluth. Another is the 15th  
30 Avenue West Substation Modernization project in west Duluth.

31

1 **Q. What is the PILC project?**

2 A. In 2012, Minnesota Power began experiencing failures on its PILC System. The five  
3 PILC circuits were constructed in the early 1920s to 1930s and operated reliably until  
4 2012. Completion of the root cause analysis concluded that the loss of mineral oil in  
5 the insulating paper of the PILCs is the underlying driver of the issues Minnesota  
6 Power is now experiencing.

7  
8 A six-year plan was developed in 2012, with work beginning in 2013, for the removal  
9 and replacement of approximately seven miles of PILCs in the Minnesota Power  
10 Distribution System in the City of Duluth. The ducts and manholes requiring  
11 replacement are primarily in two-lane downtown streets and will require close  
12 coordination with the City of Duluth. The 2016 forecast and the 2017 test year  
13 budget each include approximately \$2 million for the PILC project. Work will  
14 continue on PILC replacement for several years after the test year.

15  
16 **Q. What is the 15th Avenue West Substation Modernization project?**

17 A. The 15th Avenue West Substation is the largest single load-serving distribution  
18 substation in the Duluth area by total load, and serves one of Minnesota Power's most  
19 high-profile load pockets: downtown and central Duluth. The 15th Avenue West  
20 Substation Modernization project was designed to rebuild and modernize the existing  
21 15th Avenue West Substation, including new 14 kV switchgear on adjacent property,  
22 one new 115 kV/14 kV transformer, replacement of three 115 kV breakers and other  
23 115 kV equipment, and miscellaneous site improvements. Many of these assets  
24 within the substation are nearing the end of their useful life.

25  
26 Construction of the 15th Avenue West Substation Modernization project is expected  
27 to begin in 2016 and continue in stages through 2018. The overall cost of the project,  
28 spread over these years, is estimated to cost approximately \$8.5 million. The 15th  
29 Avenue West Substation Modernization project will ensure a continuous and reliable  
30 power supply for the downtown and central Duluth area in the most cost-effective and  
31 least-environmentally-impactful manner possible.

1                                   **2.       Advanced Metering Infrastructure and Technologies**

2   **Q.    What is AMI?**

3   A.    AMI is a two-way communication between utilities and customers that provides an  
4       integrated system of smart meters, communications networks, and data management.

5  
6       In 2007, Minnesota Power began evaluating the technology requirements for  
7       deployment of a Critical Peak Pricing rate project and evaluated both specific  
8       technological solutions as well as AMI technology solutions to support this potential  
9       rate design offering for customers. Minnesota Power determined that investment in  
10      AMI technology could meet both the needs of the Critical Peak Pricing program and  
11      help to transition to a next generation technology required to overcome some of the  
12      operating and emerging obsolescence challenges associated with the Automated  
13      Meter Reading (“AMR”) technology.

14  
15      In early 2009, Minnesota Power took the initiative to apply for funding a pilot project  
16      as part of the Department of Energy (“DOE”) American Recovery and Reinvestment  
17      Act (“ARRA”) Smart Grid Investment Grant (“SGIG”). The scope of the pilot  
18      project included deployment of AMI meters and Smart Grid technologies and  
19      infrastructure that Minnesota Power had been actively evaluating to address the  
20      obsolescence and operational challenges associated with the current AMR meter  
21      population. The Minnesota Power SGIG proposal was one of the projects selected by  
22      the DOE in 2010 and received a matching grant of approximately \$1.55 million  
23      dollars toward the total project cost of \$3.1 million dollars. The project was  
24      implemented over four years from 2010 to 2014. The scope of this pilot project  
25      included: deployment of more than 8,000 AMI meter devices and system  
26      infrastructure, establishment of a “limited” meter data warehouse, upgrade of the dual  
27      fuel system, automation of two distribution feeders located in Duluth, and  
28      incorporation of a consumer behavior study, in which the interim report was  
29      completed in March 2014, with the final report completed in August 2016.

30

1 **Q. How is Minnesota Power’s AMI being used?**

2 A. Since 2011, the Outage Management System (“OMS”) has been integrated with the  
3 Company’s AMI system. This integration provides real-time messages from the AMI  
4 system when the power goes out at the customer service and when the power is  
5 restored to a customer service. The AMI-OMS integration also allows service  
6 dispatchers to “ping” individual customer meters to verify power restoral and service  
7 status manually. This feature is integrated into the current OMS screens utilized by  
8 the dispatchers.

9

10 Overall, where the AMI system is deployed, it allows efficient metering access and  
11 enhanced communication and situational awareness between Minnesota Power and its  
12 customers. With the meters acting as “smart nodes” on each premise, a multitude of  
13 benefits can be derived, including: efficient deployment of advanced time-based  
14 customer rate offerings, outage notifications, and notification of service issues (such  
15 as low/high voltage and tamper warnings), improved load control, and more frequent  
16 customer usage data, and potentially the ability to more quickly reconnect customers  
17 who may have been involuntarily disconnected due to non-payment. The expansion  
18 of Minnesota Power’s AMI capabilities lays the groundwork for further Smart Grid  
19 initiatives and improvements to the customer experience.

20

21 **Q. How has the AMI system directly benefited customers?**

22 A. Since the AMI system installation was initiated, there have been many customer  
23 benefits realized. One of the most critical improvements is the read rate improvement  
24 versus the AMR system, which has resulted in fewer estimated bills sent to  
25 customers. The deployment of the AMI system has also led to cost savings that I  
26 discuss later in my testimony.

27

28 Another critical benefit has been the ability for the AMI system to detect an over-  
29 temperature or “hot socket” condition prior to a potential catastrophic failure at a  
30 meter socket. Minnesota Power began tracking these alarms since 2012 and has had

1 82 unique hazard alarms, 58 of which were conditions that required further action to  
2 remediate a hazard.

3  
4 **Q. Are there other potential benefits for customers from the AMI system?**

5 A. Yes. As Company witness Ms. Tina Koecher discusses in more detail, the Company  
6 is proposing to implement a pilot to reduce customer reconnection charges. This will  
7 be a significant customer benefit when Minnesota Power has the ability to reconnect  
8 customers remotely following the disconnect process. This will allow Minnesota  
9 Power to perform this traditionally manual task at a much lower cost and within a  
10 shorter time frame in a safer manner for employees as they are not exposed to  
11 electrical hazards in the process. These are just a few of the benefits that AMI has  
12 provided or can provide for customers.

13  
14 **3. Customer Service CIS/CC&B Capital Project**

15 **Q. Please describe the Customer Information System Project (“CIS Project”).**

16 A. Minnesota Power implemented a new customer information system (“CIS”) in May  
17 2015. This system is CC&B from Oracle. The Company upgraded a vintage 1994  
18 mainframe green screen system that served Minnesota Power and its customers well  
19 for twenty years. The CIS Project’s scope of functionality included billing, rates,  
20 service requests, payments, credit and collections, meter reads, and customer account  
21 maintenance. The CC&B system went live with the majority of required  
22 functionality in May 2015. Credit & collections functionality was started in CC&B in  
23 mid-June, 2015.

24  
25 The new CIS allows Minnesota Power to greatly enhance and improve its current  
26 communication with customers while establishing industry best practices. For  
27 example, a second phase to the system will feature an on-line portal for customers so  
28 that they will have increased options to not only transact with Minnesota Power over  
29 the phone, but also on-line, and provide customer self-service functionality.

30

1 **Q. Did the old CIS system create operational inefficiencies?**

2 A. The old CIS system had difficulty integrating with other systems and applications.  
3 As the CIS was developed so many years ago, programs to communicate with  
4 external systems were not part of the application as you would see with systems  
5 today. Developing and maintaining interface processes was very time consuming and  
6 labor intensive. The new CC&B system has these integration components as out-of-  
7 the-box functionality and are much easier to create and maintain.

8

9 **Q. What was the total capital cost to implement the CIS Project?**

10 A. The total capital cost to implement the CIS Project was \$19.01 million (ALLETE).<sup>23</sup>

11

12 **Q. What was Minnesota Power’s capital cost to implement the CIS Project?**

13 A. Minnesota Power’s capital addition to implement the CIS Project was \$17.38 million  
14 (Total Company). The capital incurred to implement the CIS is summarized in  
15 Table 17.

16

17

**Table 17**  
**CIS – CC&B Capital**  
**2010-2017 (Dollars in Millions)**

Actual & Budget invested in the respective year								
Description	2010 Actual	2011 Actual	2012 Actual	2013 Actual	2014 Actual	2015 Actual	2016 Forecast	2017 Budget
CIS** Replacement			\$0.27	\$7.75	\$7.79	\$1.57		

\*\*Cash flow includes the credit from SWL&P for their portion of the project.

18

19 **Q. When was the CIS Project placed in service?**

20 A. The CIS Project was placed in service in May 2015.

21

---

<sup>23</sup> The “ALLETE” naming convention includes all of ALLETE, Inc.’s subsidiaries, including its regulated and non-utility energy focused businesses.

1 **Q. What are Minnesota Power’s incremental O&M costs to operate & maintain the**  
 2 **CC&B system that are included in the 2017 test year?**

3 A. Three IT employees were hired for the CIS Project and now provide ongoing support  
 4 for CC&B. Costs of these employees are included in the 2017 test year. Software  
 5 maintenance for CC&B is also in the 2017 test year budget. These expenses are  
 6 offset by the removal of costs for the mainframe infrastructure used by the old CIS.  
 7 In 2014, mainframe-related actual costs totaled \$0.604 million dollars per year. The  
 8 associated savings are also incorporated into the O&M budget for the 2017 test year.  
 9

10 **V. POWER DELIVERY O&M EXPENSE BUDGETS**

11 **Q. Are O&M expense budgets developed annually by each function?**

12 A. Yes. Both the transmission function and the distribution function develop annual  
 13 budgets and track their individual actual expenditures. Additionally, the Vegetation  
 14 Management budget, although it is developed by the distribution function, is inclusive  
 15 of vegetation management for both the transmission and the distribution functions.  
 16 The overall Transmission and Distribution Department O&M expense budgets are  
 17 provided in Table 18.  
 18  
 19

20 **Table 18**  
**Transmission and Distribution O&M Expense**  
**2011-2017 Actuals & Budget (Dollars in Millions)**

Description	2011 Actual	2012 Actual	2013 Actual	2014 Actual	2015 Actual	2016 Forecast	2017 Budget
Transmission	\$15.80	\$16.28	\$15.50	\$16.78	\$18.02	\$20.28	\$22.64
Distribution <sup>^</sup>	\$20.20	\$18.50	\$18.67	\$20.88	\$19.88	\$20.75	\$21.64
Vegetation Management	\$4.47	\$3.55	\$4.80	\$4.21	\$4.52	\$5.25	\$5.85
Storm Restoration <sup>++,**</sup>	N/A	\$1.2	\$1.06	\$1.16	\$2.02	\$0.70**	\$0.88
++ Estimated Storm & Trouble Restoration Expense. ** Estimated Storm & Trouble Restoration Expense (Jan.-Aug.) for 2016 is \$4.19 million dollars. ^ The Vegetation Management and Storm Restoration line items are included in the Distribution total.							

1           **A.     Transmission O&M Expense Budget**

2           **Q.     What is included in the Transmission O&M expense budget?**

3           A.     The Transmission O&M budget includes expenses associated with the operation and  
4           maintenance of our transmission system. This includes internal labor, contract and  
5           consulting services, fleet, materials, and other expense categories.

6

7           **Q.     What is the Company's Transmission O&M budget for the 2017 test year?**

8           A.     We have budgeted \$22.64 million dollars for Transmission O&M in 2017, which is  
9           an increase of \$4.62 million from 2015 actual expenses.

10

11          **Q.     What is driving the increase in the Transmission O&M expense budget?**

12          A.     While we are anticipating increases in all categories of Transmission O&M expenses,  
13          the primary drivers are contract services, consulting, and labor expenses to both merit  
14          and currently-delayed hiring, fleet, and the IT/Lease expenses. Overall, these  
15          increases result from increased Transmission System needs.

16

17          The greatest contribution to the increase in the Lease and IT expense category is a  
18          result of the increase in the SWL&P Transmission Asset Lease Agreement (“TALA”)  
19          expense. In 2015, Minnesota Power paid SWL&P \$1.302 million dollars. This  
20          expense is forecasted to increase to approximately \$1.800 million dollars in 2017.  
21          This payment has been trending upward since 2010 as a result of SWL&P's  
22          investments in transmission infrastructure. The TALA defines the methodology for  
23          calculating the Minnesota Power expense for leasing the SWL&P transmission  
24          system.

25

26          We are expecting an increase of \$1.39 million in contract and consulting service  
27          expenses from 2015 actuals to the 2017 budget. This is primarily due to \$0.80  
28          million related to increased JPZ expenses to be paid to Great River Energy.

29

30          We are expecting an increase of \$0.64 million in internal labor costs from 2015  
31          actuals to the 2017 budget largely due to market salary adjustments. Some of these



1 increases are due to staffing to meet additional NERC regulatory programs and  
2 compliance.

3

4 Historic low fuel prices and Company salvage credits resulted in a lower net  
5 operating expense for Minnesota Power fleet operations in 2015. The budgeted  
6 amount of \$1.16 million dollars in 2017 is more consistent with historic spending.  
7 The fleet and strategic sourcing team continue to reduce costs. These efforts are  
8 outlined in the cost control section of my testimony.

9

10 **B. Distribution O&M Expense Budget**

11 **Q. What is included in the Distribution O&M expense budget?**

12 A. The Distribution O&M budget includes expenses associated with the operation and  
13 maintenance of our distribution system. This includes internal labor, contract  
14 services, fleet, materials, and other expense categories.

15

16 **Q. What is the Company's Distribution O&M budget for the 2017 test year?**

17 A. We have budgeted \$21.64 million dollars for Distribution O&M in 2017, which is an  
18 increase of \$1.76 million from 2015 actual expenses.

19

20 **Q. How does the 2017 budget compare to prior years?**

21 A. The 2017 Distribution O&M expense budget is similar to the 2011, 2014, and 2015  
22 actuals and the 2016 forecast.

23

24 **C. Vegetation Management**

25 **Q. What is included in the Vegetation Management O&M expense budget?**

26 A. The Vegetation Management O&M budget includes expenses associated with the  
27 pruning, removal, mowing, and application of herbicide to trees and tall-growing  
28 brush adjacent to Minnesota Power's rights-of-ways to limit preventable vegetation-  
29 related interruptions. The Company has historically operated on a routine  
30 maintenance cycle ranging between five years and six years for the distribution  
31 facilities and on a seven-year cycle for transmission facilities. This generally means

1 that vegetation around our electric facilities will be maintained on a routine rotating  
2 cycle by circuit. It also includes what is referred to as “hot spotting,” where specific  
3 areas or trees are addressed outside of the normal vegetation cycle on an “as needed”  
4 basis to address specific concerns (“danger trees” or “trees on wire”) identified by  
5 customers or company employees.  
6

7 **Q. What is the Company’s Vegetation Management O&M budget for the 2017 test**  
8 **year?**

9 A. We have budgeted \$5.85 million dollars for Vegetation Management O&M in 2017,  
10 which is an increase of \$1.3 million from 2015 actual expenses due to the need to  
11 increase our vegetation management efforts to maintain the reliability and operation  
12 of our Transmission System and Distribution System.  
13

14 **Q. Has Minnesota Power accrued any lessons learned based on its six-year**  
15 **vegetation maintenance cycle?**

16 A. Minnesota Power implemented an expense savings initiative in 2011 that focused on  
17 establishing longer-term strategic sourcing contracts with fewer vegetation  
18 management contractors. This initiative resulted in Minnesota Power securing more  
19 competitive pricing through bidding the entire Minnesota Power vegetation  
20 distribution maintenance cycle for all 330 circuits over a six-year contract term.  
21 These were firm price bids for each of the 330 specific circuits.  
22

23 The Company and the contractors have both acknowledged that the six-year term was  
24 likely too long. It was difficult for the parties to fully anticipate the challenges  
25 associated with changing priorities when responding to unplanned storm events.  
26 Minnesota Power has identified the need for more flexibility to address particular  
27 circuits requiring action sooner than others based on environmental factors related to  
28 weather (i.e., variable growing seasons, micro-climate conditions impacted by  
29 moisture, temperatures, and vegetation types). These factors have shaped and  
30 influenced Minnesota Power to determine that future contract terms should not  
31 exceed three years for future vegetation management bid packages. Minnesota Power

1 acknowledges that the five-year maintenance cycle is an industry best practice goal  
2 and is incorporating additional funding necessary to achieve that objective  
3 incrementally over the next five years. Minnesota Power will revise our future SRSQ  
4 reports to list our circuits that fall outside of the suggested five-year cycle as outlined  
5 in the Commission's Order issued April 7, 2006, in Docket No. E015/M-05-554.  
6

7 **Q. Are other factors contributing to the increase in the vegetation management  
8 expense budget in 2016 and 2017 as compared to the 2015 actuals?**

9 A. Minnesota Power is completing the final two years of the six-year contract and both  
10 the 2016 and the 2017 budgets reflect some of the more difficult and complex  
11 distribution circuits that are physically more challenging and expensive to access and  
12 also include longer circuit miles. The 2016 and 2017 years also reflect the higher  
13 expenses due to shorter contract terms. The 2017 budget includes the expenses  
14 necessary to transition the distribution vegetative cycle over the next five years from  
15 a six-year to five-year cycle. This objective can be achieved along with maintaining  
16 the seven-year vegetation cycle for transmission facilities by maintaining the current  
17 budget levels included in the 2017 test year over the next four years (2018 through  
18 2022).  
19

20 **D. Storm Restoration**

21 **Q. Are there any new O&M categories that Minnesota Power is seeking to include  
22 in its O&M expense budget?**

23 A. Yes. For the first time, Minnesota Power is seeking to include Storm Restoration in  
24 its O&M expense budget. I note that the amounts included in the Storm Response  
25 line of Table 18 are amounts that were included in 2011 to 2015 distribution actuals  
26 and included in the 2016 forecast and the 2017 budget. In addition, these are not  
27 amounts budgeted *for* storm response, but are amounts budgeted for overtime. Only  
28 the storm response amount noted in 2015 includes additional incremental O&M costs  
29 beyond internal overtime labor.  
30

1 **Q. How has Minnesota Power historically handled storm response from a financial**  
2 **perspective?**

3 A. Minnesota Power has not historically budgeted for storm response. In prior years, the  
4 historic response to “trouble” events (which includes storm response overtime) has  
5 almost exclusively been addressed by the Minnesota Power line workers who are all  
6 budgeted in the distribution function responsibility cost center (“RC” or “RC 190”).  
7 This had been the Company’s operating experience for the past 15 years. Minnesota  
8 Power has successfully restored service to customers following other significant  
9 storm events and had not needed to request mutual assistance from other utility  
10 partners for over 15 years prior to July 12, 2015.

11  
12 **Q. How much did the Duluth/North Gull Lake Storm on July 21, 2016, cost the**  
13 **Company?**

14 A. We are still waiting to receive final billings from some of our mutual aid partners  
15 who assisted in the July storm restoration effort. However, our latest estimate is  
16 approximately \$5.7 million (Total Company) dollars in total costs (combined  
17 Company capital and associated O&M). Although the July 2016 storm work order  
18 reconciliation and final accounting adjustments are still pending, we are estimating  
19 the incremental O&M component to be approximately \$2.929 million dollars. Given  
20 the increase in storm restoration costs in recent years, in 2016, the Company filed a  
21 petition for deferred accounting treatment related to storm response (Docket No.  
22 E015/M-16-648) in an effort to recover costs incurred to restore the Minnesota Power  
23 Transmission System and Distribution System after the July 2016 storm.

24  
25 **Q. How did Minnesota Power estimate a historic “storm & trouble” restoration**  
26 **amount for use in this rate case?**

27 A. The methodology that Minnesota Power is using to determine the total annual amount  
28 of incremental O&M storm restoration expense is detailed in Exhibit \_\_\_ (CEF),  
29 Schedule 4. The information provided in Exhibit \_\_ (CEF), Schedule 4 provides the  
30 actual overtime expense that RC 190 line workers worked from 2010 to 2015.

31

1 Based on this, we believe that it is prudent to establish a “storm and trouble” response  
2 budget as part of this rate review. This budget would include storm expenses,  
3 including the smaller weather-related events that are currently handled by overtime  
4 from RC 190.

5

6 **Q. What is the annual funding amount that Minnesota Power is proposing for**  
7 **establishing the storm restoration budget?**

8 A. Minnesota Power is requesting authority to establish a “storm and trouble” restoration  
9 budget amount total of \$2.474 million dollars per year. Minnesota Power has already  
10 budgeted in 2017, in the RC 190, \$0.876 million dollars for O&M Overtime Labor  
11 Expense that would become part of the new storm budget. The net impact would be  
12 an additional increase of \$1.598 million dollars of O&M expenses (per year) to be  
13 added into the distribution function. The methodology that Minnesota Power used to  
14 determine the total annual amount of incremental O&M storm restoration expense of  
15 \$2.474 million dollars is detailed in Exhibit \_\_ (CEF), Schedule 4. The requested  
16 amount is calculated by averaging the last three years of incremental O&M (2014,  
17 2015, and 2016 estimated). The incremental amount required to establish a “storm  
18 and trouble” restoration budget amount has not been included in the 2016 forecast or  
19 2017 test year budget in this rate case given the timing of when this issue arose in  
20 2016 for the Company. The Company will provide and incorporate the additional  
21 amount in its Rebuttal Testimony updates in this rate review.

22

23

## **VI. OTHER COMPLIANCE REQUIREMENTS**

24

### **A. FERC Return on Equity**

25

**Q. Please explain the relevance of the pending FERC proceedings in FERC dockets**  
26 **E114-12-000 and E115-45-000.**

27

A. In November 2013, a group of customers filed a complaint at FERC against MISO  
28 transmission owners, including the Minnesota Power system (Docket No. EL14-12-  
29 000). The complaint argued for a reduction in the ROE in transmission formula rates  
30 in the MISO region from 12.38 percent to 9.15 percent, a prohibition on capital  
31 structures in excess of 50 percent equity, and the removal of ROE incentive adders.

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29

FERC initiated hearing procedures regarding the appropriate ROE to be used in MISO transmission owner formula rates and established a November 12, 2013, refund effective date. Hearings were held during August 2015. An Administrative Law Judge (“ALJ”) initial decision of 10.32 percent was issued and a FERC Order was issued on September 28, 2016, confirming that 10.32 percent was the appropriate ROE for the MISO transmission owners.

A separate group of customers filed an additional complaint in February 2015 proposing to reduce the MISO region ROE to 8.67 percent (Docket No. EL15-8-000). FERC has established a refund effective date of February 12, 2015 for this second complaint and has initiated hearing procedures. Hearings were held in February 2016, and an initial ALJ decision of 9.7 percent was issued June 30, 2016. FERC estimated it would issue an order at the end of May 2017.

**Q. Have the MISO transmission owners filed any requests?**

A. In November 2014, the MISO transmission owners filed a request for FERC approval of a 50 basis point ROE incentive adder for participation in the MISO Regional Transmission Organization (“RTO”). In January 2015, FERC approved the request, effective January 6, 2015, and subject to the outcome of the ROE complaints. This incentive adder will be added to the ROE ordered by FERC in the outstanding complaints, with the limitation that the final ROE, including the incentive adder, cannot exceed the upper limit of the range of reasonableness to be established in the ROE complaints. The FERC Order approved an ROE of 10.32 percent, less than the previously-authorized ROE of 12.38 percent. A reduction in the ROE used in transmission formula rates will result in decreased wholesale transmission revenues, net of third-party transmission expenses, thereby reducing the resulting revenue credit to Minnesota customers.

1 **Q. What ROE was assumed for purposes of this case?**

2 A. The 2017 test year budget for wholesale transmission revenue and third-party  
3 transmission expense was prepared based on the currently-authorized FERC ROE of  
4 12.38 percent. However, the Company was accruing for the anticipated reduction in  
5 revenues and expenses based on the recommendation of the ALJ (10.32 percent),<sup>24</sup>  
6 which is the same ROE FERC ordered in September 2016. Therefore, no adjustments  
7 need to be made to the 2017 test year budget based on this FERC order.

8

9 **B. MISO Participation**

10 **Q. Please describe the 2017 Minnesota Power system third-party transmission**  
11 **expenses and revenue.**

12 A. There are several types of third-party costs. These are Minnesota Power transmission  
13 costs necessary to serve Minnesota Power Transmission System loads, including  
14 Minnesota Power retail native loads in Minnesota, pursuant to rate schedules accepted  
15 for filing by FERC. The Minnesota Power transmission system is part of the regional  
16 transmission system planned by MISO.

17

18 **Q. Does Minnesota Power have any compliance items related to its participation in**  
19 **MISO?**

20 A. Yes. In Docket Nos. E999/AA-09-961 and E999/AA-10-884, the Commission  
21 required all utilities to continue to show benefits of participation in MISO in their rate  
22 proceedings.

23

24 **Q. What are the benefits of Minnesota Power's participation in MISO?**

25 A. Minnesota Power participates in the MISO Day-Ahead, Real-Time, and Ancillary  
26 Services Market. Minnesota Power's generation is dispatched in response to MISO  
27 market price signals. This has allowed Minnesota Power to use its generation  
28 resources to meet customer needs when Minnesota Power generation is the lowest-  
29 cost resource and to reduce its generation and purchase energy in the wholesale

---

<sup>24</sup> This recommendation does not include the 50 basis point adder that Minnesota Power is allowed to earn in addition to this 10.32 percent ROE.

1 market when market energy is the lowest-cost resource. As a result, the MISO  
2 market structure has allowed Minnesota Power to continue to make extensive use of  
3 the wholesale power market to secure low-cost energy for its customers.

4  
5 Other benefits of the MISO market include increased purchase options, more  
6 transparent pricing, and the ability to purchase only the amount of energy needed  
7 each hour rather than buying energy blocks provided by a traditional bilateral market.  
8 MISO also performs certain NERC compliance responsibilities on behalf of all  
9 transmission owners, in lieu of each transmission owner having to complete these  
10 responsibilities. All of these benefits have provided savings for our retail customers.  
11 The benefits of MISO have more than offset the additional cost incurred to implement  
12 the market. In addition, the MISO market allows Minnesota Power and other MISO  
13 members access to an expansive footprint consisting of a diverse set of generation  
14 and transmission resources, which, when coupled with appropriate rules and an  
15 independent market monitoring function, fosters a robust wholesale energy market.

16  
17 **Q. What are the 2017 test year wholesale transmission revenues?**

18 A. As shown in Exhibit \_\_\_ (CEF), Schedule 5 to my Direct Testimony, the total  
19 Minnesota Power system 2017 test-year wholesale net revenues are estimated to be  
20 \$1.44 million dollars, an increase from (\$4.29) million dollars in 2015 (an expense).  
21 The negative values in 2015 and 2016 reflect Minnesota Power's accrual to account  
22 for the potential refunds to wholesale customers resulting from the FERC ROE  
23 complaints.

24

25 **VII. COST CONTAINMENT EFFORTS**

26 **Q. What cost containment efforts has the Transmission and Distribution**  
27 **Department undertaken since the Company's last rate review?**

28 A. All groups within the Transmission and Distribution Department routinely work to  
29 identify ways in which we can complete our jobs more efficiently, and cost  
30 containment is inherent in that analysis. In addition to headcount reductions  
31 discussed by Company witness Ms. Nicole Johnson in her Direct Testimony and



1 reductions identified by Company witness Mr. Steven Morris in his Direct  
2 Testimony, the Transmission and Distribution Department has undertaken several  
3 other cost containment efforts consistent with Order Point 15 in our last rate case  
4 (Docket No. E015/GR-09-1151). These efforts are in the areas of the CC&B savings  
5 I mentioned earlier in my testimony, fleet costs, service center consolidations,  
6 electronic payment processing convenience fees for customers, and meter operations.  
7 These are summarized in Exhibit \_\_\_\_ (CEF), Schedule 6 to my Direct Testimony.  
8 Cost savings that have been identified by the Transmission and Distribution  
9 Department are reflected in our 2017 O&M budgets.

10  
11 **Q. What actions has the Transmission and Distribution Department taken with**  
12 **respect to fleet costs?**

13 **A.** Minnesota Power has worked closely with our fleet operations and purchasing teams  
14 to evaluate the savings potential between leasing our fleet vehicles and purchasing  
15 them. As noted in my earlier testimony, Minnesota Power will begin transitioning to  
16 purchasing fleet vehicles over the next seven years, and away from our historic  
17 practice of using operating leases. We have included an additional capital category  
18 beginning in the budget year 2017 for \$5.4 million dollars. This will provide a Net  
19 Present Value (“NPV”) savings to our operations and ultimately for customers of \$3.0  
20 million dollars and an annual benefit of \$0.158 million dollars per year (over 30  
21 years). The first year savings is estimated to be approximately \$19,000. The savings  
22 anticipated for 2017 have been incorporated into the fleet budget.

23  
24 **Q. Are there other actions that fleet operations has taken to reduce expenses for**  
25 **customers?**

26 **A.** Fleet operations has initiated a series of initiatives to reduce the operating cost, which  
27 ultimately translates into reduced costs for our customers. These initiatives are listed  
28 as “Fleet Costs” in Exhibit \_\_\_\_ (CEF), Schedule 6 to my Direct Testimony.

29

1 **Q. Please explain how the closure of service centers will result in cost reductions for**  
2 **the Company.**

3 A. Minnesota Power initiated and completed an evaluation of the Minnesota Power  
4 service center locations in late 2014. The study was completed in May of 2015 with  
5 recommendations for a phased repositioning. Phase 1 recommended closure of three  
6 of the existing service centers (Nisswa, Aurora, and Chisholm). The locations are  
7 identified in Exhibit \_\_\_ (CEF), Schedule 7 to my Direct Testimony. The service  
8 center employees were notified in July 2015 that their new reporting locations would  
9 be effective on October 1, 2015. The closure of these three service centers was  
10 justified on the net O&M savings and avoided capital investments. The savings  
11 analysis factored in the potential inefficiencies with planned capital work and  
12 possible customer impacts to service quality.

13  
14 The Company anticipated that the service center consolidation would also support  
15 implementing a more robust crew scheduling at the remaining service centers and the  
16 deployment of technology to mitigate some of the potential customer service quality  
17 concerns. The service center closure plan did not result in worker reductions. The  
18 goal was to take the smaller staffed service centers and combine them so that a larger  
19 number of employees were consolidated at the remaining service center facilities.  
20 This provides more opportunity for straight-time coverage during the week and a  
21 larger number of line workers to draw on for “trouble” call out coverage. The  
22 closures result in \$2.2 million in avoided capital costs. The O&M savings are  
23 estimated at between \$36,000 and \$90,000 dollars per year.

24  
25 Minnesota Power will continue to serve the communities’ and customers’ energy  
26 needs but under a new delivery model that improves our efficiency and effectiveness.

27  
28 **Q. What cost savings have been achieved through the Company’s AMI**  
29 **deployment?**

30 A. First, in deploying the AMI system, the Company identified, in 2012, the opportunity  
31 to save \$0.28 million by purchasing AMI meters for load research instead of those

1 purchased in earlier stages of the project. Second, the use of the AMI system resulted  
2 in a \$0.15 million annual savings for the Company's Dual Fuel program. The AMI  
3 platform reduced the required annual capital by \$0.15 million associated with  
4 expensive disconnect switches that were no longer needed. The AMI also provided  
5 an annual O&M savings of \$0.05 million per year because of simplified asset  
6 management requirements.

7

8 **Q. What has the Company done with respect to electronic payment processing**  
9 **convenience fees for customers?**

10 A. Starting in July of 2012, Minnesota Power renegotiated our payment processing  
11 agreement with our payment processing vendor for customers electronically paying  
12 their monthly bills. Prior to 2012, if a customer paid their monthly bill electronically,  
13 they were charged a \$3.50 per-transaction convenience fee. As part of this  
14 renegotiation, Minnesota Power was able to reduce this fee to \$2.95 per transaction.  
15 We began tracking and quantifying cost savings in 2013 and have determined that  
16 this renegotiated agreement results in a savings of \$50,000 to \$60,000 per year for our  
17 customers. The Company has proposed a new program to allow customers to pay  
18 their monthly bills by debit or credit card without the individual per-transaction fee,  
19 as discussed in more detail by Company witness Ms. Tina Koecher.

20

21 **Q. Are there other cost savings measures that have been undertaken by the**  
22 **Transmission and Distribution Department that are not quantified in your**  
23 **testimony?**

24 A. Yes. As discussed by Company witness Mr. Morris, each department within the  
25 Company is continuously monitoring its operations to identify ways in which cost  
26 containment measures may be initiated or ways we can more efficiently serve our  
27 customers. For example, the T&D leaders initiated a review of the number and  
28 justification for determining which employees should be authorized for "take home"  
29 or "call out" vehicles. This resulted in T&D reducing the number of essential "take  
30 home" vehicles by over 30 in August 2015. We also implemented a vehicle idling  
31 policy with all power delivery employees in May 2015, encouraging employees to

1 turn off their vehicles upon arriving at their work sites (except under extreme weather  
2 conditions) in an effort to save fuel and reduce emissions. In alignment with our  
3 idling policy, our fleet group took action to ensure that all “warning strobe and hazard  
4 lights” on all line trucks and other fleet vehicle classes could be operated by battery  
5 without the risk of running the battery down while parked along a road side. These  
6 two actions resulted in noticeable saving in fuel consumption.

7  
8 We are also piloting the use of iPads for our substation inspections and are observing  
9 efficiency gains and savings associated with improved record keeping and more  
10 timely identification of maintenance and corrective work as well as higher employee  
11 satisfaction. We also committed to IT that this group of employees would only use  
12 one mobile device. The iPad is for emails, entering time, completing expense reports,  
13 etc. The iPad also eliminates the need for a laptop.

14  
15 **Q. Are there any broader cost containment efforts that the Transmission and**  
16 **Distribution Department has initiated?**

17 A. Yes. In conjunction with the ALLETE Human Resources team, the Transmission and  
18 Distribution Department has initiated a lean Six Sigma “green-belt” training program.  
19 Six Sigma is a set of techniques and tools for process improvement. While we are  
20 just beginning this initiative, it further supports our efforts for continuous  
21 improvement of our business practices. At this time, we have graduated over a dozen  
22 champions and green belts in the Transmission and Distribution Department.

23  
24 **VIII. CONCLUSION**

25 **Q. Does this conclude your Direct Testimony?**

26 A. Yes.


**Transmission Capital Investment Table\*\***  
**2010 - 2017 (Dollars in Millions)**

Category Description	2010 Actual	2011 Actual	2012 Actual	2013 Actual	2014 Actual	2015 Actual	2016 Forecast	2017 Budget	Total
<b>Transmission Base:</b>	\$ 16.51	\$ 11.18	\$ 10.62	\$ 23.20	\$ 10.72	\$ 10.77	\$ 17.43	\$ 20.07	\$ 120.50
<b>Reliability Requirement:</b>									
NERC - Facility Rating		\$ 0.02	\$ 3.22	\$ 20.20	\$ 22.00	\$ 12.94	\$ 10.25		\$ 68.63
North Shore Loop				\$ (0.19)		\$ 0.77	\$ 7.67	\$ 11.83	\$ 20.08
Badoura*	\$ 2.53	\$ (0.43)		\$ (0.07)					\$ 2.03
Savanna*			\$1.09	\$3.22		\$0.16	\$0.61		\$ 5.08
Deer River			\$ 0.03	\$ 0.44	\$ 6.61	\$ 8.12	\$ 0.56	\$ 0.89	\$ 16.65
Straight River						\$ 0.02	\$ 2.49		\$ 2.51
Dog Lake <sup>+</sup>							\$ 1.35	\$ 2.78	\$ 4.13
<b>Total Reliability Requirement:</b>	\$ 2.53	\$ (0.41)	\$ 4.34	\$ 23.60	\$ 28.61	\$ 22.01	\$ 22.93	\$ 15.50	\$ 119.11
<b>New Business / Customer:</b>									
Nashwauk	\$ 0.02	\$ 6.25	\$ 24.38	\$ 1.97		\$ (1.51)	\$ 0.01	\$ 0.02	\$ 31.14
39-Line			\$ 0.15	\$ 2.11	\$ 3.49	\$ 0.02			\$ 5.77
Canisteco				\$ 0.37	\$ 11.99	\$ 0.76			\$ 13.12
<b>Total New Business/Customer:</b>	\$ 0.02	\$ 6.25	\$ 24.53	\$ 4.45	\$ 15.48	\$ (0.73)	\$ 0.01	\$ 0.02	\$ 50.03
<b>Regional Expansion:</b>									
Bemidji 230 kV*	\$ 1.64	\$ 5.12	\$ 4.20	\$ (0.06)	\$ (0.01)	\$ (0.01)			\$ 10.88
Fargo 345 kV*	\$ 7.78	\$ 11.40	\$ 19.41	\$ 35.56	\$ 22.77	\$ 2.70	\$ 0.50		\$ 100.12
Great Northern Transmission <sup>+</sup>		\$ 0.07	\$ 1.34	\$ 1.32	\$ 2.96	\$ 5.19	\$ 20.50	\$ 117.15	\$ 148.53
<b>Total Regional Expansion:</b>	\$ 9.42	\$ 16.59	\$ 24.95	\$ 36.82	\$ 25.72	\$ 7.88	\$ 21.00	\$ 117.15	\$ 259.53
<b>Other:</b>	\$ 4.00		\$ 2.10	\$ 9.42	\$ 4.65	\$ 3.18			\$ 23.35
<b>Total</b>	\$ 32.48	\$ 33.61	\$ 66.54	\$ 97.49	\$ 85.18	\$ 43.11	\$ 61.37	\$ 152.74	\$ 572.52

\*Denotes projects currently (or a portion thereof) in-service and in the Minnesota Power Transmission Cost Recovery Rider - requesting to move into base rates.

+Denotes projects that are Transmission Cost Recovery Rider-eligible that will not be placed in service until 2017 or later and are not part of the base rate request.

\*\* This table includes 2010 to 2015 actual capital additions, 2016 forecasted capital additions, and 2017 budget capital additions.



TCR Rider recovery.<sup>7</sup> We believe our proposed inclusion of the Buffalo Ridge restoration project costs in the 2011 tracker is consistent with this past practice, assuming the Commission agrees the Buffalo Ridge project is eligible for TCR Rider recovery.

#### 4. *Insurance Proceeds and Other Compensation*

The Department indicated the Company should be allowed to request recovery of the Buffalo Ridge restoration costs in our next rate case, but recommended the Commission require the Company to provide information in that rate case about whether we received any insurance proceeds, other compensation, or a reduction in taxes as a result of the storm damage. We provide the information below to assure the Commission that granting recovery of the Buffalo Ridge restoration costs through the TCR Rider will not result in double recovery.

We will not receive any insurance proceeds related to the storm damage. The Company does not purchase insurance covering storm damage to either our transmission system or distribution lines. From time to time, we investigate the availability and cost of such insurance, but both factors indicate that purchasing a policy would be prohibitively expensive for our customers. For example, the last time the Company investigated such insurance, the premium for each \$1 million of coverage was approximately \$300,000 per year. That cost would be included in rates. While there are electric utilities that purchase such coverage, they are all located in hurricane prone areas. Since the Company experiences large scale damage less frequently than utilities in hurricane zones, and given the cost of insurance coverage, it is less expensive to our customers over the long term for the Company to repair damage to our transmission system caused by storms as it occurs than to purchase insurance.

Further, the Company has not received and does not expect to receive other compensation or a tax reduction that would offset the Buffalo Ridge restoration costs. As such, it is not necessary for the Commission to require a compliance report in the Company's next rate case.

#### **C. Project Costs for Bemidji and Brookings CapX2020 Projects**

The Department recommends that the Commission impose a "cost cap" on TCR Rider recovery of the cost of the CapX2020 Bemidji project, and requests further information regarding whether certain costs were included in the CapX2020

---

<sup>7</sup> April 27, 2010 Order at p. 4-5.

Brookings project. The Company requests that the Commission and Department consider the following reply.

1. *Certificate of Need Cost Estimate Caps*

While certain Commission orders have imposed caps on costs recovered through the TCR Riders, the statutes enabling utilities to recover transmission and renewable investments through these riders contain no provisions for such caps. As such, we believe the Commission can consider in this case whether the use of cost caps continues to be appropriate.

The Commission first considered the issue of a cost cap on a transmission project in Docket No E002/M-10-1048 related to the Blue Lake-Wilmarth 345 kV line, where the Company sought recovery under the RCR Statute. The Commission did not allow recovery in the TCR Rider of the anticipated \$1.7 increase on a project initially expected to cost \$6 million. The Company did not ask the Commission to reconsider the decision at the time. This was in part because we received a contribution in aid of construction which reduced our total investment to less than \$6 million, meaning the Company's total investment was ultimately less than the cap.

We also recognize there may be circumstances where using cost caps on rider recovery could be appropriate. For example, the Commission initially established the cost cap concept when considering RES rider recovery of the Nobles wind project costs. The Commission limited RES Rider recovery to the cost estimates in the original Certificate of Need estimate, and ruled that costs above that level would be reviewed for possible inclusion in a subsequent rate case subject to a prudence determination. Part of the Commission's reasoning was that the initial project cost estimates were those used in a bidding process where the Nobles project competed against other generation projects. As costs were a factor related to competition with other generation projects, the Commission determined allowing RES Rider recovery of increased project costs was not appropriate without additional review in a rate case.

We do not believe, however, the same rationale is applicable to eligible transmission projects. While cost is considered in determining whether a transmission line is needed, more important are reliability and customer demand considerations. We move forward with transmission projects when needed to meet demand or improve reliability, and utilities are the only entities allowed to construct such facilities.

One of the reasons the Legislature enacted the TCR Statute to allow rider recovery was because it recognized the complexity of the transmission permitting, siting, routing, and construction process and length of time required to complete projects.



Imposing a cap on rider recovery and deferring review of certain costs to a future rate case is contrary to the intent of the statute. The estimates we include in a Certificate of Need (CON) application are outdated by the time we begin seeking rider recovery of costs for eligible transmission projects. To facilitate the need determination, we provide high-level planning cost estimates. Detailed design and engineering is not performed at this stage in order to minimize total costs in the event the CON is not granted. Permitting, land acquisition, and ancillary project costs are difficult to predict during this initial phase as well, as the route and pole alignments are not known.<sup>8</sup>

The Legislature foresaw significant investment in transmission was needed to accommodate projected new electric generating capacity when enacting the TCR Statute. To encourage the Company and other utilities to invest in transmission facilities, the Legislature provided the Commission with the authority to grant cost recovery through a rider outside of a general rate case. The Commission was authorized to approve an annual cost recovery mechanism and make prudence determinations as part of those proceedings. As noted, the TCR Statute provides:

the commission shall approve the annual rate adjustments provided that, after notice and comment, the costs included for recovery through the tariff *were or are expected to be prudently incurred* and achieve transmission system improvements at the lowest feasible and prudent cost to ratepayers.  
(Emphasis added.)

The Department comments do not assert that specific project costs were not prudently incurred. Indeed, the Commission has never previously determined any Company transmission project costs to be ineligible for rate recovery as imprudent, and we believe the estimated Bemidji project costs reflected in our TCR Rider petition can be expected to be prudent. Our annual TCR Rider proceedings can be the appropriate forum for making any prudence determination. Alternatively, if the Commission prefers, however, prudence review for individual projects could be deferred to the rate case after a project is placed in service. However, under the “expected to be prudently incurred” standard in the TCR Statute, the Commission should not disallow TCR Rider recovery of the costs of eligible projects if there is no assertion of imprudence.

---

<sup>8</sup> While not the norm, the Company has on occasion not included the routing, permitting, and siting-related costs in a certificate of need proceeding for a transmission project that involves a complex routing project. For example, the cost estimates provided in the recently approved Hiawatha 115 kV transmission project did not contain these costs during consideration of the certificate of need. It was not until the final route had been approved that these costs were able to be reasonably quantified and included in the total project costs. Even when such costs are included in a certificate of need application, the estimates generally will not be able to reflect all federal, state, and tribal permitting complexities, or siting and land acquisition details.

We appreciate that the Department's comments indicating some flexibility in the level of costs allowed in the TCR Rider may be appropriate. For example, the Department indicates use of an appropriate escalator to reflect increasing costs over time, or allowing recovery of additional costs incurred due to unforeseen or extraordinary circumstances may be appropriate.

However, as we make significant transmission investments going forward – for example, we plan to invest over \$1 billion in the CapX2020 projects – the TCR Rider mechanism for recovering these costs is important to provide the benefit intended by the statutes. The statutes were designed to promote investment in the transmission system to improve reliability and access to renewable generation for our customers. Allowing TCR Rider to recover the capital costs incurred between rate cases is consistent with the intent of the legislation. For these reasons, we believe the Commission should reconsider whether cost caps are appropriate for major transmission projects or alternatively, how they should be established.

In light of these policy considerations, we discuss further below the specific cost increase related to the Bemidji project. We believe this additional information demonstrates our concern with applying the “cost cap” principle to individual transmission projects, and demonstrates that recovery of Bemidji project costs in 2012 TCR Rider rates should not be capped at the level in the 2007 Certificate of Need application, even adjusted for a cost escalator.

## 2. *Bemidji Project*

### a. Eligible Project Costs

The Bemidji Project is a 70 mile 230 kV transmission line between Bemidji and Grand Rapids that will address reliability concerns in this area. Under the CapX2020 collaborative development arrangements, Otter Tail Power was designated the project manager and prepared and filed the Certificate of Need application in 2007 with assistance by the other CapX2020 project participants, including Xcel Energy. (Docket No. E017, E015 & ET-6/CN-07-1222). The project is currently approximately 98 percent complete, and the first segment of the project was energized in August 2011.

At the time of the Certificate of Need application in 2007, the estimated cost of the Bemidji project cost was \$60.6 million (2007 dollars). At the time of the route permit proceeding in 2007 (Docket No. E017, E015 & ET-6/TL-07-1317) the projected cost as approved was estimated to be \$66.2 million (2007 dollars). We now estimate the

total cost of the project to be approximately \$116 million.<sup>9</sup> The cost to construct the transmission line and substation – the facilities granted a Certificate of Need -- is approximately \$89.5 million.

We recognize that these cost increases are significant; however, the estimates provided in the Certificate of Need application were based on Otter Tail Power’s transmission estimation methodology at that time. While escalating costs over time account for part of the increase, the table below identifies other additional project costs. We also provide a discussion of the project costs, including cost increases that could not have been estimated at the time of the Certificate of Need application, that are necessary for completion of the project.

Table 1  
 Bemidji Project Cost Comparison  
 (\$millions)

Cost Component from Route Permit Exhibit ___ (REL), Schedule 2	Certificate of Need	Route Permit	Current Forecast	Change over Route Permit
<b>Transmission Facilities</b>				
Base Cost for 230 kV Line		\$44.80	\$53.54	\$8.14
230/115 kV Double-Circuit Adder at Wilton		\$0.60	In above	In above
Woodland Adder		\$4.60	\$5.58	\$0.98
Winter Construction Adder (includes mat procurement)		\$5.80	\$15.40	\$9.60
Pipeline Induction Management Costs			\$1.94	\$1.94
<b>Transmission Line Subtotal</b>	\$58.10	\$55.80	\$76.46	\$20.66

<sup>9</sup> This current projection is less than the \$123 million estimate provided in our Petition filed in January 2012.

Cost Component from Route Permit Exhibit ___ (REL), Schedule 2	Certificate of Need	Route Permit	Current Forecast	Change over Route Permit
<b>Associated Facilities</b>				
Boswell Substation Expansion		\$1.00	\$0.89	(\$0.11)
Wilton Substation Expansion		\$1.50	\$1.24	(\$0.26)
Cass Lake Substation Expansion		\$5.20	\$5.70	\$0.50
Nary Breaker Station		\$2.70	\$2.25	(\$0.45)
Ottertail Power Underlying Facilities			\$0.24	\$0.24
Minnesota Power Underlying Facilities			\$0.05	\$0.05
Nary to Cass Lake OTP			\$1.60	\$1.60
Nary to Cass Lake MPC			\$1.05	\$1.05
<b>Associated Facilities Subtotal</b>	\$2.50	\$10.40	\$13.02	\$2.62
<b>Permitting, Right of Way and Legal</b>				
CON and Route Permit Permitting Costs			\$9.10	\$9.10
Post permit legal fees			\$3.22	\$3.22
Environmental Permitting and Compliance			\$8.38	\$8.38
Right of Way			\$5.70	\$5.70
CapX2020 Joint Sourcing and Management			\$0.50	\$0.50
<b>Total</b>			\$26.90	\$26.90
<b>Transmission Line and Facilities Total</b>	\$60.60	\$66.20	\$116.38	\$50.18

The following discussion describes the cost increases (or decreases) related to the Bemidji Project:

## Transmission Facilities

- *Winter Construction Adder.* The Project incurred \$15.4 million to purchase, install and remove additional wetland protection mats due to warm winter temperatures during 2011-2012, which was \$9.6 million more than originally estimated. During normal winters, wetlands in the area freeze so that construction with typical protective measures can continue. This past winter was one of the warmest on record and the wetlands in the project area did not freeze sufficiently to support construction equipment. Continuing construction was more cost-effective than waiting until spring but required additional equipment to protect the wetland areas against damage from heavy traffic and use of construction equipment. To protect the landscape, the Project purchased, installed, and removed an additional 20,000 mats.
- *Tree clearing and Road Restoration.* The Project has incurred approximately \$5.6 million thus far. This is an increase of approximately \$1.0 million over what was originally estimated. Trees along the route were larger and more dense than anticipated.
- *Pipeline Induction Mitigation.* Electric transmission lines located near natural gas or oil pipelines can induce electrical currents across the pipeline facilities, which can reduce the effectiveness of the pipeline's corrosion protection system. Portions of the Bemidji Project parallel the Great Lakes Gas Transmission natural gas pipeline along U.S. Highway 2. As a result, the project needed to install special equipment to protect the pipeline facilities. The Project incurred approximately \$1.9 million to perform pipeline induction mitigation. This cost was not estimated at the time of the Certificate of Need or Route Permit applications because it was dependent on route alignment and determination of the specifics of the protective techniques required. However, the cost is essential to the safe operation of both the electric and pipeline facilities.
- *Transmission Line Construction.* The cost to construct the transmission line facilities is now estimated to cost approximately \$8.1 million more than the \$45.4 million estimate (2007 dollars) provided during the Route Permit proceeding. It is common for facility cost estimates to be updated using the Handy Whitman Index, an industry index specifically used to estimate the impacts of inflation on transmission projects over time. Applying the Handy Whitman index values for the 2007 to 2012 period to the \$45.3 million estimate would result in an estimated cost increase of \$8.2 million, slightly more than the current estimate. See Attachment C. Therefore, the increase in transmission line construction costs over the five years since the route permit was issued is consistent with (or slightly less than) the results experienced for similar

transmission projects, demonstrating the increases are reasonable.

### **Associated Facilities**

The costs of the substation facilities associated with the Bemidji 230 kV line have increased approximately \$2.6 million from the estimate provided in the Route Permit application. For those associated facilities that were individually identified and a cost estimate was provided, the costs have actually decreased slightly. The overall increase in cost in this category is thus due to several additional associated facilities that were identified as being needed for the project to be reliably interconnected to substations and the underlying transmission system.

### **Permitting, Right of Way and Legal**

As discussed in the Petition, the costs associated with this category of project costs were expected in the regulatory approval processes; however, the specific value of these costs were not quantified at the time of project approval in the Certificate of Need or Route Permit applications. These costs include:

- *Certificate of Need and Route Permit Costs.* The Project has spent approximately \$9.1 million on activities to obtain the permits to proceed with this project, including the Certificate of Need and Route Permit.
- *Post Permit Legal Fees.* The Project has spent approximately \$3.2 million on legal fees since the Certificate of Need and Route Permit were granted. This includes the legal fees to litigate our dispute with the Leech Lake Band of Ojibwe (the Tribe) over the route through tribal land, and to obtain and comply with permits. At the time the project applied for a Certificate of Need, we did not foresee a protracted litigation would be needed to site this project and reach the best outcome for all parties involved.
- *Environmental Permitting and Compliance.* Approximately \$8.4 million has been spent on environmental permitting and compliance matters. For example, this includes \$2.2 million paid to the U.S. Forest Service for permits, wetland restoration, hunting and gathering rights for the Tribe and agency monitoring.
- *Right of Way.* Approximately \$5.7 million was spent to acquire easements to construct this project. It was specifically noted in the Certificate of Need application that right of way costs would be incurred but the costs not included in the cost estimate.

We believe all of the costs incurred to date for the Bemidji Project are necessary to complete the project, were prudently incurred and are in the public interest. The CapX2020 entities have taken all of the steps needed to construct and route a successful transmission project. The cost increases meet the “prudent or expected to be prudent” standard in the TCR Statute, and the actual cost of the project (not the 2007 estimate, even if it were adjusted) should provide the basis for the TCR Rider cost recovery.

b. A Cost Cap Should Not be Applied Retroactively

Even if the Commission were to decide to continue to apply the cost cap principle to TCR eligible projects, it would be inappropriate to apply such a cap to the CapX2020 Bemidji project. At the time the project applicants submitted the Certificate of Need application for the Bemidji line in 2007, the Commission had not applied a cost cap to a TCR eligible project. The Commission did not apply this principle to a transmission project until its April 2010 order regarding the Wilmarth/Blue Lake line. Thus, the project applicants could not have known the Commission might later seek to limit TCR Rider rate recovery to the estimates in the CON or Route Permit applications. It would be arbitrary and capricious to apply the cost cap ratemaking principle where the Certificate of Need application was submitted and approved before the Commission ever announced the cost cap principle.

Moreover, while the Bemidji project Certificate of Need estimates did not include cost estimates for all necessary work and permitting, the fact that the project would incur some additional costs was disclosed and known.<sup>10</sup> Consistent with Certificate of Need and Route Permitting practice at that time, the project applicants provided high-level estimates to construct the transmission line along various route alternatives. It is not feasible to estimate costs to the granularity needed for rate making purposes when a route and the issues associated with constructing a transmission line are not known.

c. Cost Cap Alternatives

We recognize that the Commission may nonetheless cap TCR Rider recovery of the Bemidji Project costs linked to the initial cost estimates provided by the project applicants during the Certificate of Need proceeding. If so, we respectfully request that the Commission consider two adjustments to the 2007 initial cost estimates.

---

<sup>10</sup> Environmental Report, Bemidji – Grand Rapids 230 kV Transmission Project, Docket No. E017, E015, ET-6/CN-07-1222, Page 5

First, the Department suggested use of an escalator for the Bemidji cost estimates. We appreciate this recommendation. As discussed previously, we believe the appropriate escalator is the Handy Whitman index for transmission projects, rather than escalation factors based on GDP or CPI. Based on the Handy Whitman index, the cost estimate for the Bemidji Project in 2012 dollars is approximately \$8.2 million higher, or \$74 million, compared to the original cost estimate of \$66.2 million contained in the Route Permit proceeding.

Second, this escalated 2012 estimate does not include additional critical costs – several of which the project applicants had no way of foreseeing – that were necessary and prudent to effectuate the project and actually place it in service in 2012. When the Commission first applied the cost cap principle to the Wilmarth/Blue Lake project in our 2010 TCR Rider proceeding, the Commission provided for the recovery of costs in excess of the project cap when such costs are unforeseeable and extraordinary. We believe the Bemidji Project costs eligible for TCR Rider recovery should include the unforeseeable or extraordinary events provided in the table above. Specifically the \$9.6 million of additional winter construction costs incurred due to a record warm winter was an unforeseen and extraordinary situation, as were the \$3.2 million of post permit legal fees. This adjustment is reasonable and would bring the cost of the project eligible for TCR Rider recovery to approximately \$87.2 million.

Again, while we believe it is unreasonable to retroactively apply the cost cap principle to a transmission project approved before the Commission adopted the concept of applying cost caps to project costs recovered through the TCR Riders, if the Commission nonetheless orders a limit on TCR Rider recoveries for the Bemidji project, the cost cap for the Bemidji project should be no lower than \$87.2 million.

### *3. Brookings Project*

Our Petition identified \$30 million in necessary system underbuild upgrades for the CapX2020 Brookings Project. The Department requested that we clarify whether this \$30 million is included in or in addition to the \$70-100 million cost range provided in the CapX2020 Certificate of Need proceeding for underbuild upgrades for the three CapX2020 345 kV projects. We confirm that the \$30 million is a part of the \$70-100 million estimate – it is the portion of that total required for the Brookings project underbuild upgrades. As such, we believe these costs for the Brookings project are recoverable in the TCR, even if the Commission were to impose a Certificate of Need cost estimate cap to the Brookings project.



**Storm Response Cost Information  
 2010 - 2017 Actuals & Budget (Dollars)**

Row No.	Estimated Historic Incremental O&M Storm & Trouble Restoration Expenses	2010 Actual	2011 Actual	2012 Actual	2013 Actual	2014 Actual	2015 # Actual & (Est.)++	2016 # YTD & (Est.)++	2017 (Budget)++
1	Total - Overtime OT Labor Expense**	\$ 1,458,990	\$1,456,992	\$ 1,533,656	\$ 1,426,756	\$ 1,649,668	\$ 1,791,769	\$ 1,907,657	N/A
2	Total - Stipends / OT Meal Expense**	\$ 19,227	\$ 21,960	\$ 54,212	\$ 29,980	\$ 20,593	\$ 87,910	\$ 78,424	N/A
3	Total - Prearranged OT Labor (Planned Overtime)**	N/A	N/A	\$ 93,642	\$ 126,710	\$ 213,799	\$ 209,490	\$ 98,761	N/A
4	Unplanned - Overtime OT Labor Expense	N/A	N/A	\$ 1,440,014	\$ 1,300,045	\$ 1,435,869	\$ 1,582,278	\$ 1,808,896	N/A
5	Unplanned - Employee Stipends / OT Meals Expense	N/A	N/A	\$ 50,902	\$ 27,317	\$ 17,924	\$ 77,631	\$ 74,364	N/A
6	Unplanned - Total Overtime Labor & OT Expenses	N/A	N/A	\$ 1,490,916	\$ 1,327,363	\$ 1,453,793	\$ 1,659,910	\$ 1,883,259	N/A
7	O&M - Overtime Labor & OT Expense*	N/A+	N/A+	\$ 1,192,733	\$ 1,061,890	\$ 1,163,035	N/A#	N/A#	N/A#
8	O&M - Overtime Labor & OT Expense - Estimated++						\$ 1,139,219	\$ 1,139,219	\$ 1,139,219
9	O&M - Actual Storm (Nisswa - July 12, 2015)!						\$ 876,788		
10	O&M - Actual Storm (Duluth / North Gull Lake - July 21, 2016)!							\$ 2,929,088	
11	O&M - Actual Storm (Nisswa / Pine River - August 4, 2016)!							\$ 118,223	
12	O&M - Total Storm & Trouble Restoration Expense	N/A+	N/A+	\$ 1,192,733	\$ 1,061,890	\$ 1,163,035	\$ 2,016,007	\$ 4,186,530	
13	O&M - Overtime Budget for Line workers (RC-190)**	\$ 1,004,550	\$ 512,000	\$ 518,000	\$ 800,000	\$ 825,000	\$ 696,300	\$ 696,300	\$ 876,300
14	O&M - Variance (Budget to Actual)	N/A		\$ (674,733)	\$ (261,890)	\$ (338,035)	\$ (1,319,707)	\$ (3,490,230)	

Notes:

- ++ Average O&M Based on 2012 - 2014 Actuals \$ 1,139,219
- \* Estimated Historic O&M vs. Capital - "Call out" 80%
- \*\* OAG IR # 003 - MP Response (MPUC Docket No. E015/M-16-648)
- # Denotes 2015 and 2016 when MP requested Mutual Aid for Storm Events
- ! O&M Actual Incremental Expenses for Storm Events Noted in 2015 & 2016
- + Prearranged / Planned OT was not tracked separately in 2010 and 2011 in the previous MP accounting system all OT was included in the total RC 190
- # Denotes 2015 and 2016 when MP request Mutual Aid for Storm Events

Worksheet Formulas:	
R4 = R1 - R3	R7 = R6 * 80%
R5 = (R4 / R1) * R2	R8 = Average(R7) - 2012, 2013, 2014
R6 = R4 + R5	R12 = R7 + R8 + R9 + R10 + R11

**Minnesota Power Third-Party Transmission Expenses and Revenues  
2010 - 2017 (Dollars in Millions)**

<b>Category Description</b>	<b>2010 Actual</b>	<b>2011 Actual</b>	<b>2012 Actual</b>	<b>2013 Actual</b>	<b>2014 Actual</b>	<b>2015 Actual</b>	<b>2016 Budget</b>	<b>2017 Budget</b>
<b>Third-Party Transmission Expenses</b>								
JPZ Payments				\$15.49	\$45.95	\$46.97	\$45.36	\$44.05
MISO Network, Firm, and Non Firm Service (AC Sched 7, 8, & 9)	\$5.68	\$4.54	\$4.01	\$4.17	\$5.07	\$5.85	\$4.51	\$5.78
HVDC Firm & Non Firm Service (HVDC Sched 7 & 8)	\$8.75	\$8.43	\$8.93	\$9.09	\$9.87	\$12.95	\$15.48	\$12.89
NERC Required (Sched 45)					\$5.05	\$9.88	\$10.21	\$10.10
MISO Admin Charges (Sched 10 & 45)	\$2.24	\$2.69	\$2.89	\$2.45	\$2.52	\$2.67	\$2.59	\$2.51
Other-Ancillary Services/LBA Services, etc. (Sched 1&2)	\$1.76	\$1.73	\$1.86	\$1.97	\$1.89	\$1.83	\$1.97	\$2.11
<b>Total Third-Party Transmission Expenses</b>	<b>\$18.43</b>	<b>\$17.39</b>	<b>\$17.69</b>	<b>\$33.17</b>	<b>\$70.35</b>	<b>\$80.15</b>	<b>\$80.12</b>	<b>\$77.44</b>
<b>Third-Party Transmission Revenues</b>								
Expired NITSA Revenue	\$0.59	\$0.53	\$0.53	\$0.35				
JPZ Revenue				\$12.38	\$39.22	\$43.45	\$41.90	\$39.96
MISO Network, Firm, and Non Firm Service (AC Sched 7, 8, & 9)	\$10.62	\$5.91	\$4.69	\$4.61	\$7.23	\$0.17	\$6.00	\$10.30
HVDC Firm and Non Firm Service (HVDC Sched 7 & 8)	\$16.13	\$15.87	\$16.36	\$18.38	\$15.71	\$14.15	\$15.48	\$12.88
NERC Required (Sched 45)					\$7.72	\$13.86	\$12.23	\$11.68
GFAs	\$2.53	\$1.80	\$1.04	\$1.07	\$1.09	\$1.06	\$1.06	\$1.06
Other-Ancillary Services/LBA Services, etc. (Sched 1&2)	\$1.97	\$2.31	\$4.37	\$3.70	\$3.16	\$3.17	\$2.76	\$3.00
<b>Total Third-Party Transmission Revenues</b>	<b>31.84</b>	<b>26.42</b>	<b>26.99</b>	<b>40.49</b>	<b>74.13</b>	<b>75.86</b>	<b>79.43</b>	<b>78.88</b>
<b>Net Revenue (Expense)</b>	<b>\$13.41</b>	<b>\$9.03</b>	<b>\$9.30</b>	<b>\$7.32</b>	<b>\$3.78</b>	<b>(\$4.29)</b>	<b>(\$0.69)</b>	<b>\$1.44</b>

**Minnesota Power Summary of Quantifiable Cost Controls and Savings**

Docket No. E015/GR-09-1151 Commission Order dated 11/2/2010, page 71, Order Point 15:

"Include testimony about efforts to control costs, including list of cost reductions made, identification of which cost reductions are permanent, and quantification of total cost savings."

Initiative	Description	Date of Action Taken	Savings Estimate	Basis for Estimate	Temporary, One-Time, or Permanent?	Witness Testimony
Electric Meter Operations	Capital reduction of 80% annually and O&M savings per year for Dual Fuel System upkeep after changing to AMI and simplified asset management related to the two-way system	2010	\$150,000 less annual Capital Requirements and \$50,000 annually less O&M Expense	Elimination of Dual Fuel Capital and Maintenance Portion of budget	Permanent	Chris Fleege
Electric Meter Operations	Completed Load Research metering project with 30% less capital than previous load research project. Purchase of AMI Meters for Load Research vs. One-Time Use Load Research Meters (American Innovation Modules) - AMI were lower cost and have a much longer asset life than our previous project.	2012	\$280,000	List cost of the AIM Load Research Modules installed in 2003 vs. The AMI Load Research Meters installed in 2012/13	Permanent	Chris Fleege
Engineering	The Distribution Service Representatives in the area doing the General Ledger Work Orders is a savings on mileage of approximately 7% per year Mileage reduction in the form of every other month staff meetings and heavily encouraging ride sharing to all 2012 out of town meetings	2014	Approximately \$10,000 annually	Internal Calculation	Permanent	Chris Fleege
Fleet Costs	Identified 19 vehicles for removal from fleet.	2015	\$1.03 M	Annual lease expense of the vehicles was \$127,000, total replacement cost avoidance is \$1.03M	Permanent	Chris Fleege
Fleet Costs	Reduced one fleet position permanently	2015	\$79,000	Labor savings	Permanent	Chris Fleege
Fleet Costs	Fleet position staffed one day a week	2015	\$60,000	Labor savings	One-Time	Chris Fleege
Fleet Costs	Obtained warranty coverage on service invoices	2015	\$12,000	OEM vendors	One-Time	Chris Fleege
Fleet Costs	Refurbished instead of replacing line tensioner tool	2015	\$56,000	Internal calculation	One-Time	Chris Fleege

\*Note that this list includes those items the Company could reliably quantify per the Commission's Order Point. Testimony addresses additional cost reductions efforts.

**Minnesota Power Summary of Quantifiable Cost Controls and Savings**

Docket No. E015/GR-09-1151 Commission Order dated 11/2/2010, page 71, Order Point 15:

"Include testimony about efforts to control costs, including list of cost reductions made, identification of which cost reductions are permanent, and quantification of total cost savings."

Initiative	Description	Date of Action Taken	Savings Estimate	Basis for Estimate	Temporary, One-Time, or Permanent?	Witness Testimony
Fleet Costs	Internal up fitting for Spacekap pod installation vs external up fitting; Ability to reuse Spacekap at next replacement	2015	\$29,000 \$591,000	Internal calculation	One-Time	Chris Fleege
Fleet Costs	Body transfer vs new build	2016	\$40,000	Internal calculation	One-Time	Chris Fleege
Service Center Consolidation	Consolidation of Nisswa, Aurora and Chisholm Service Centers. Other consolidations are being studied.	Jul-15	\$2.2 million avoided capital investments; O&M savings approximately \$36,000 to \$90,000 annually	Avoid identified capital investments at closed facilities; reduced overtime associated with deeper crew availability at consolidation locations.	Permanent	Chris Fleege
Upgrade Customer Information System to use corporate standard systems	Upgraded Customer Information System to use corporate standard Oracle database and corporate standard Exalogic Server. Enabled dropping support for Adabase database and the IBM mainframe	2015	\$604,498	Budget cost savings associated with no longer operating the Mainframe.	Permanent	Chris Fleege
Western Union Initiative	Negotiated a reduction in one-time convenience fee for MP customers for electronic payments. Reduces the amount paid by the customer	July 2012	\$50,000-\$60,000 per year (costs quantified beginning January 1, 2013)	Internal Calculation	Permanent	Chris Fleege

\*Note that this list includes those items the Company could reliably quantify per the Commission's Order Point. Testimony addresses additional cost reductions efforts.

